

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-081-00376-0000

API NUMBER Not Applicable

LEASE NAME Boatright #2

WELL NUMBER #2

2310' Ft. from S Section Line

3960' Ft. from E Section Line

SEC. 13 TWP. 29 SRGE. 32 (E) of (W)

COUNTY Haskell County

Date Well Completed 9-5-55

Plugging Commenced 1-24-89

Plugging Completed 1-24-89

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR KANSAS NATURAL GAS, INC.

ADDRESS P.O. Box #818 Hays, Kansas 67601

PHONE# (913) 625-7353 OPERATORS LICENSE NO. #5269

Character of Well Chase Series - Casing Collapsed

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on January 10, 1989 (date)

by Mr. Steve Durrant - Dodge City, Kansas (KCC District Agent's Name).

Is ACO-1 filed? yes If not, is well log attached? _____

Producing Formation Chase Series Depth to Top 2668' Bottom 2708' T.D. 2720'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Fresh water	8 5/8"	Surfac	565'	8 5/8"	565'	
	5 1/2"	Surfac	2720'	5 1/2"	2720'	

RECEIVED
STATE CORPORATION COMMISSION

MAY 18 1989

5-18-1989
CONSERVATION DIVISION
Wichita, Kansas

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set. Ran tubing to a depth of 1848' and cement first plug at that point. Pulled 10 joints to 1448' and ran another 35 sks of Class H cement for plug. Pulled another 17 joints and set at 448' and cements with 50 sacks of Class H cement to surface, and cottonseedhulls. Pumped a total of 215 sacks of Class H 60-40 posmix with 300# of cottonseed hulls.
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor DOWELL SCHLUMBERGER License No. -----

Address Ulysses, Kansas 67880

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: KANSAS NATURAL GAS, INC.

STATE OF KANSAS COUNTY OF Ellis COUNTY, ss.

Alan R. Hoffman (Employee of Operator) or (Operator) o above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Alan R. Hoffman

(Address) P. O. Box 818, Hays, KS 67601

SUBSCRIBED AND SWORN TO before me this 1st day of May, 19 89

Kraig L. Gross
Notary Public

My Commission Expires: May 8, 1990

