

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

#1 API NUMBER 15-081-20,526-0000

LEASE NAME Boatright #3

WELL NUMBER #3

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

4030' Ft. from S Section Line

1250' Ft. from E Section Line

SEC. 13 TWP. 29S RGE. 32W(E) or (W)

COUNTY Haskell County

LEASE OPERATOR KANSAS NATURAL GAS, INC.

ADDRESS P.O. Box #818 Hays, Kansas 67601

PHONE#(913) 625-7353 OPERATORS LICENSE NO. #5269

Date Well Completed 4-11-89

Character of Well Chase Series - Wet.

Plugging Commenced 9-27-89

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 9-27-89

The plugging proposal was approved on 9-26-89 (date)

by Mr. Steve Durrant - Dodge City, Kansas (KCC District Agent's Name).

Is ACO-1 filed? yes If not, is well log attached? _____

Producing Formation Chase Series Depth to Top 2693' Bottom 2722' T.D. 2750'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Fresh Water	8 5/8"	Surface	571'	8 5/8"	571'	
	5 1/2"	Surface	2750'	5 1/2"	2750'	

RECEIVED
STATE CORPORATION COMMISSION
OCT 03 1989
10-3-1989
CONSERVATION DIVISION
Wichita, Kansas

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Pumped 40/60 Pox (H) cement with 6% Bentonite and cottonseed hulls to bottom of production perforations (approx. 2730') and set a 30 sack plug. Pulled tubing to approximately 1875' (bottom of anhydrites) and set a 20 sack plug. Pull tubing to approximately 580' (bottom of surface) and set a 20 sack plug. Pull tubing to 30' from surface and set a 10 sack plug to sur-
(If additional description is necessary, use BACK of this form.)
Witness for the Kcc was Mr. Richard Lacy of Dodge City.

Name of Plugging Contractor DOWELL SCHLUMBERGER License No. -----

Address Ulysses, Kansas 67880

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: KANSAS NATURAL GAS, INC.

STATE OF KANSAS COUNTY OF HASKELL COUNTY, ss.

Steve Lehning - Kansas Natural Gas, Inc. (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Steve Lehning

(Address) P.O. Box #815 Sublette, Mo.



Subscribed AND SWORN TO before me this 2 day of Oct., 19 89

C.A. Myers
Notary Public

My Commission Expires: 2-11-93