

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE NAME Howell

WELL NUMBER Unit #1

3960 Ft. from S Section Line

3960 Ft. from E Section Line

SEC. 11 TWP. 29S RGE. 32W (E) or (W)

COUNTY Haskell

Date Well Completed 12-10-1954

Plugging Commenced 11-27-1995

Plugging Completed 11-27-1995

LEASE OPERATOR American Warrior, Inc.

ADDRESS P.O. Box 399, Garden City, KS. 67846

PHONE# (316) 275-2963 OPERATORS LICENSE NO. 4058

Character of Well GAS

(Oil, (Gas) D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on October 13, 1995 (date)

by District #1 - Richard Lacey (KCC District Agent's Name).

Is ACO-1 filed? YES if not, is well log attached? _____

Producing Formation Hugoton Depth to Top 2650 Bottom 2690 T.D. 2700

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
	Surface	surface	452	8-5/8"	452	NONE
	Production	surface	2715	5-1/2"	2715	NONE

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from _____ feet to _____ feet each set pump 200# of hulls, 25 sks 60/40 poz 6% gel, displaced to 2500' perforated @ 700' pump 225 dkd cement, cement did not circulate, hook-up to 8-5/8" pump 100 sks cement ISIP 200# top off 5-1/2" casing cut off 6' below ground level fill cellar.

Name of Plugging Contractor Southwest Well Service

Address P.O. Box 399 Garden City, KS. 67846

RECEIVED
STATE CORPORATION COMMISSION
License No. _____

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: American Warrior, Inc.

STATE OF Kansas COUNTY OF Finney, ss.

NOV 30 1995
11-30-1995
CONSERVATION DIVISION
Wichita, Kansas

Kevin Wiles Sr.


(Employee of Operator) or (Operator) :

above-described well, being first duly sworn on oath, says that I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

(Signature) Kevin Wiles Sr.

(Address) P.O. Box 399, Garden City, KS. 67846

SUBSCRIBED AND SWORN TO before me this 20th day of Nov, 1995



Debra J. Purcell
Notary Public