


15-081-00001-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

HASKELL County. Sec. 18 Twp. 29S Rge. 31W (R) (W)
Location as "NE/CNW/SW" or footage from lines CNL SW
Lease Owner GRAHAM-MICHAELIS DRILLING CO.
Lease Name CLARK Well No. 1
Office Address 211 North Broadway, Wichita, Ks.
Character of Well (completed as Oil, Gas or Dry Hole) ~~XXXXXXXX~~ Gas
Date well completed 1-21-55 19
Application for plugging filed 10-21-57 19
Application for plugging approved 11-23-57 19
Plugging commenced 11-23-57 19
Plugging completed 11-26-57 19
Reason for abandonment of well or producing formation ~~XXXXXXXX~~
Low Production
If a producing well is abandoned, date of last production May 19 57
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Merle Rives, Box 8, Pratt, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 2687 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS				CASING RECORD		
FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
<u>Sand, Gravel, & Sandy shale</u>		<u>0</u>	<u>541*</u>	<u>8 5/8"</u>	<u>541*</u>	<u>0</u>
<u>Shale, Red Bed & Sand, Anhy., Gyp & lime</u>		<u>0</u>	<u>2681*</u>	<u>5 1/2"</u>	<u>2681*</u>	<u>1405*</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged back w/crushed rock to 2670*, dumped 5 sax cement @2670* w/dump bailer. Top of cement, 2640*. Filled hole w/mud to 540*, set rock bridge, dumped 20 sax cement. Top of cement, 480*. Filled w/mud to 35*, set rock bridge, dumped 10 sax cement for cap.

DEC 13 1957
CONSERVATION DIVISION
Wichita, Kansas
12-13-1957

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Miller Casing Pulling Company
Address P. O. Box 711, Great Bend, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
O. W. Woodland (employee of owner) ~~and owner or operator~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. Graham-Michaelis Drilling Co.

(Signature) O. W. Woodland
211 No. Broadway, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 11th day of December, 1957

F. D. Grier
Notary Public.

My commission expires 1/7/61

PLUGGING
FILE SEC. 18 T. 29 R. 31W
BOOK. PAGE 55 LINE 15

CLARK NO. 1

Well Record

Location: Approx. 1320' W. of
C/ Sec. 18-29S-31W
Haskell County, Kansas

Commenced: Jan. 17, 1955
Completed: Jan. 21, 1955

Operator: Michaelis Drilling Company
1019 East Second Street
Wichita, Kansas

Contractor: Michaelis Drilling Company
1010 East Second Street
Wichita, Kansas

Casing Record: 8 5/8" @ 541 W/ 300 sacks cement
5 1/2" @ 2681 W/ 166 sacks cement

LOG

Sand & gravel	420
Sandy shale	530
Shale	544
Shale & red bed	1110
Red bed	1320
Sand	1495
Red bed & anhydrite	1525
Red bed & gyp	1910
Anhydrite & red bed	2010
Line	2800
Anhydrite & sandy shale	3087, RTD
Top Herrington	2680

The undersigned, W. A. MICHAELIS, JR., hereby certifies that the above log is a true and correct log of the formations encountered in drilling the above well as reflected by the Daily Drilling Report.

MICHAELIS DRILLING COMPANY

By W. A. Michaelis, Jr.
W. A. MICHAELIS, JR.

STATE OF KANSAS)
) ss.
COUNTY OF SEDGWICK)

Subscribed and sworn to before me this 1st day of February, 1955.

My commission expires: Nov. 7, 1957.

Mary L. Barnes
Notary Public.

OCT 22 1957
CONSERVATION DIVISION
Wichita, Kansas

PLUGGIN
FILE SEC 18 T 29 3W
BOOK PAGE 55 LINE 15