

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Biting Building  
Wichita, Kansas

Haskell County, Sec. 1 Twp. 29S Rge. (E) 32 (W)

Location as "NE/CNW $\frac{1}{4}$ /SW $\frac{1}{4}$ " or footage from lines SW $\frac{1}{4}$  SW $\frac{1}{4}$  NW $\frac{1}{4}$

Lease Owner Skelly Oil Company

Lease Name M. C. Hull Well No. 1

Office Address Box 1650, Tulsa, Oklahoma

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed November 9, 1951

Application for plugging filed November 9, 1951

Application for plugging approved Nov. 13, 1951

Plugging commenced Nov. 10, 1951

Plugging completed Nov. 10, 1951

Reason for abandonment of well or producing formation Volume of gas in this well not sufficient for commercial value

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes (verbally)

Name of Conservation Agent who supervised plugging of this well Mr. R. J. Phillippe

Producing formation Krider Lime Depth to top 2720' Bottom 2744' Total Depth of Well 2782' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	OD Size	Put In	Pulled Out
Krider Lime	Gas	2720'	2744'	10-3/4"	716'3"	None
				6"	2765'3"	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

- Plastic 2782' to 2775 $\frac{1}{2}$ '
- Bridging plug 2640'
- 250 sacks of cement 2640' to 1453'
- 100 sacks of cement 1453' to 600'
- Mud laden fluid 600' to 25'
- 6 sacks of cement 25' to 6'
- Surface soil 6' to 0'

STATE COMMISSION

NOV 23 1951

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Kuhn Drilling Company  
Address Union Nat'l. Bank Building  
Wichita, Kansas

STATE OF Kansas, COUNTY OF Reno, ss.  
H. E. Wamsley (employee of owner) or (owner/operator) of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

Box 391, Hutchinson, Kansas  
(Address)

SUBSCRIBED AND SWORN to before me this 21st day of November 21, 1951

My commission expires April 7, 1955

Josephine S. Johnson  
Notary Public.

