


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Kiowa County. Sec. 24 Twp. 29 S Rge. (E) 16 (W)
Location as "NE/CNW/SW" or footage from lines SW/4 SW/4 NW/4 (twin)
Lease Owner Messman-Rinehart Oil Company
Lease Name Piester Well No. 1
Office Address 518 Petroleum Building, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed March 22 19 55
Application for plugging filed November 5 19 60
Application for plugging approved November 7 19 60
Plugging commenced December 31 19 60
Plugging completed January 5 19 61
Reason for abandonment of well or producing formation Depleted reservoir

If a producing well is abandoned, date of last production September 29 19 60
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well W. L. Lackamp, Stafford, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4675 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	343'	none
				5-1/2"	4675'	3959'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Bailed fluid and set Cal-seal plug at 340 ft.,
Plug did not hold, mixed and ran 1 sk. Cal-seal
on plug at 340 ft. followed with 20 sx. cement
by dump bailer. Mudded hole to 40 ft., set 10 ft.
rock bridge with 10 sx. cement to base of cellar

RECEIVED
STATE CORPORATION COMMISSION

FEB 10 1961

CONSERVATION DIVISION
Wichita, Kansas

2-10-61

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Southwest Casing Pulling Co., - License No. 399
Address Great Bend, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
J. A. Gilliland (employee of owner) or ~~(owner)~~ of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

518 Petroleum Building, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 19th day of January, 1961

My commission expires December 1, 1964

Barbara J. Scott
Barbara J. Scott, Notary Public.

K

NO. 1 PIESTER

WELL RECORD

Location: App SW SW NW, 24-29S-16W
Kiowa County, Kansas

Commenced: February 26, 1955

Operator: Grauehart-Miller Oil Company
1005 East Second, Wichita, Kansas

Completed: March 16, 1955

Contractor: Graham-Messman-Rinehart Oil Company
1005 East Second, Wichita, Kansas

Elevation: 1943 KB

Production: Oil

Casing Record: 8 5/8" @ 343' w/175 sacks cement
5 1/2" @ 4675' w/75 sacks cement

....L O G....

Sand-Gravel	26
Shale	140
Sand (Fine)	170
Shale	838
Anhydrite	853
Shale	1795
Ft. Riley	2106
Line-Shale	2265
Shale-Line	2407
Line-Shale	2660
Shale-Line	2795
Line-Shale	3906
Line	3992
Line-Shale	4215
Line-Chert	4321
Line	4347
Line-chert	4394
Line	4591
Line-Chert	4604
Mississippi	4616
Miss.-Chert	4636
Congl.-Shale	4661
Shale	4675 R.T.D.

RECEIVED
STATE CORPORATION COMMISSION

FEB 10 1961

CONSERVATION DIVISION
Wichita, Kansas

Sample Tops:

Heebner 3879 (-1936)
Brown Line 4044 (-2101)
Douglas Sand 3932 (-1989)
Lansing 4061 (-2118)
Penn. Sand 4568 (-2633)
Mississippi 4596 (-2653)
Base Miss. 4636 (-2693)

The undersigned, GRAHAM-MESSMAN-RINEHART OIL COMPANY, hereby certifies that the above log is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Report.

GRAHAM-MESSMAN-RINEHART OIL COMPANY

By: J. A. Gilliland
J. A. Gilliland

Subscribed and sworn to before me
this 22nd day of March 1955.

Marion L. Lewis
Notary Public

My Commission Expires: November 5, 1958

G.M.R.
FEB 20 1961