


15-095-01289-00-00

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

NORTH



Locate well correctly on above  
Section Plat

Kingman County, Sec. 11 Twp. 29 Rge. 9 (E) W. (W)  
Location as "NE/CNW/SW" or footage from lines Gen. SW NE SW  
Lease Owner: Cities Service Oil Company  
Lease Name: Amsden Well No. 3  
Office Address: Great Bend, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed October 23, 19 54  
Application for plugging filed October 23, 19 54  
Application for plugging approved October 23, 19 54  
Plugging commenced October 23, 19 54  
Plugging completed October 23, 19 54  
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Ruel Durkee  
Producing formation Viola Depth to top 4506 Bottom 4536 Total Depth of Well 4536 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	304'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

4536-260', heavy mud.  
260-200', wood plug, rock bridge, hulls and 20 sacks cement.  
200- 35', heavy mud.  
35' to base of cellar, wood plug and 10 sacks cement.

11-6-54  
RECEIVED  
DIVISION  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Barbour Drilling Company  
Address Tulsa, Oklahoma

STATE OF Kansas, COUNTY OF Barton, ss.  
V. M. Conover (employee of owner) or (owner/proprietor) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) V.M. Conover  
Box 751, Great Bend, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 5th day of November, 19 54

My commission expires March 12, 1955. Notary Public.

PLUGGING  
FILE SEC 11 T 29 R 9W  
BOOK PAGE 22 LINE 30

# WELL RECORD

Company Cities Service Oil Co. Well No. 3 Farm Abandon  
 Location 990' South and 990' West of Center Sec. 11 T. 29 R. 9W  
 Elevation 1699 (1696 Gr.) County Kingsan State Kansas  
 Drlg. Comm. October 7, 1954 Contractor Barbour Drilling Company  
 Drlg. Comp. October 23, 1954 Acid None  
 T. D. 4536' Initial Prod. Dry Hole - Plugged and Abandon 10-23-54

CASING RECORD:

8-5/8" @ 304' cas, 250 wt cement

FORMATION RECORD:

soil and sand	0-140
red bed & shale	305
red bed & shells	750
shale & shells	1795
shale & lime	1970
lime & shale	2090
shale & lime	2450
shale	2615
shale & lime	2800
lime & shale	2875
shale & lime	2990
lime & shale	3085
lime	3340
lime & shale	3550
shale & lime	3600
lime	4065
lime & shale	4160
lime	4229
chert	4250
cherty lime & shale	4289
lime	4320
lime & shale	4360
shale	4506
lime	4511
chert	4516
lime	4536 T. D.

Hobner	3343'
Lansing	3553'
Mississippi	4208'
Kinderhook	4323'
Viola	4506'
Penetration	30'
Total Depth	4536'

D. S. T. 4209-23, open 1 hr.,  
recovered 65' muddy salt water;  
B. H. P. 1380#/30 mins.

D. S. T. 4507-11, open 1 hr.,  
recovered 150' oily mud and 60'  
salt water; B. H. P. 1500#/30  
mins.

D. S. T. 4511-16, open 1 hr.,  
recovered 900' water-cut oil and  
730' salt water; B. H. P. 1500#/  
30 mins.

SYFO:	500'	0°
	1000'	0°
	1500'	1°
	2000'	0°
	2500'	1°
	3000'	1°
	3500'	0°
	4000'	0°

RECEIVED  
STATE GEOLOGICAL COMMISSION

107-6 1954  
CONSERVATION DIVISION  
-Wichita, Kansas

**PLUGGING**  
 FILE SEC 11 T 29 R 9W  
 BOOK PAGE 22 LINE 30