


15-095-01803-00-00

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Plat

Kingman County. Sec. 11 Twp. 29 Rge. 9 (W)  
Location as "NE/CNW/SW" or footage from lines NE/SW/SW  
Lease Owner Aurora Gasoline Company  
Lease Name Amsden Well No. #2  
Office Address 1107 Union National Bldg. Wichita 2, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) \_\_\_\_\_  
Date well completed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging filed Yes 19\_\_\_\_  
Application for plugging approved Yes 19\_\_\_\_  
Plugging commenced \_\_\_\_\_ 10-9 19 58  
Plugging completed \_\_\_\_\_ 10-13 19 58  
Reason for abandonment of well or producing formation \_\_\_\_\_

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Fred Hampel  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4539' Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	Surface	
				5 1/2"		3,604'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Measured into T.D. 4539'.  
Plugging started 10-9-58. Finished 10-13-58.  
Plugged off bottom and sanded back to 4485'. Dumped 5 sacks cement and worked pipe. Shot 5 1/2" casing at 3,604'. Pumped mud. Squeezed well, using 100 sacks cement. Well completed.

Name of Plugging Contractor J.O. Forbes d/b/a Forbes Casing Pulling Co.  
Address Box 221, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.  
J.O. Forbes (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J.O. Forbes  
Box 221, Great Bend, Kan. (Address)

SUBSCRIBED AND SWORN TO before me this 22 day of October, 1958

My commission expires November 8, 1960.

Betty S. Edman Notary Public.

RECEIVED  
STATE CORPORATION COMMISSION

PLUGGING  
FILE SEC 11 T 29 R 9W  
BOOK PAGE 133 LINE 45

10-24-58 OCT 24 1958

CONSERVATION DIVISION  
Wichita, Kansas

AMSDEN #2

Casing Record:  
 8 5/8" - 118'  
 5 1/2" - 4539'

COMPANY: Aylward Drilling Co. and  
 Aurora Gasoline Company

Location: NE SW SW Sec. 11-  
 29-9W  
 Kingman County, Kansas

CONTRACTOR: Aylward Drilling Company

COMMENCED: September 10, 1954  
 COMPLETED: SEPTEMBER 23, 1954

Elevation: 1698 D.F.  
 1700 K.B.

	<u>From</u>	<u>To</u>	<u>Remarks</u>
Cement	100	130	8 5/8" Casing set @ 118' w/100 sacks Pozmix and 1 CC
Red Bed & Shale	130	600	
Shale and Shells	600	1270	
Salt	1270	1375	
Anhydrite & Lime	1375	1495	GEOLOGICAL TOPS: Heebner 3334 Toronto 3354 Douglas 3374 Lansing 3560 Mississippian 4210 Viola 4503
Lime & Shale	1495	2190	
Lime	2190	2385	
Shale	2385	2435	
Lime & Shale	2435	2670	
Lime	2670	2770	
Lime & Shale	2770	3605	
Lime	3605	4205	
Chat Lime	4205	4305	
Lime	4305	4390	
Shale & Lime	4390	4503	
Viola	4053	4510	5 1/2" casing set @ 4539 w/150 sacks T.D. Pozmix
Viola Lime	4510	4539	

Cable Tool Data:  
 Moved in and perforated 40 holes. 4503 to 4512. Put on pump.

RECEIVED  
 STATE CORPORATION COMMISSION

OCT 8 1958

PLUGGING  
 FILE SEC. 11 T. 29 R. 9W  
 BOOK PAGE 133 LINE 45