


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

15-095-00546-00-00
WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Kingman County. Sec. 11 Twp. 29 Rge. 9 (E) W (W)
Location as "NE/CNW/SW" or footage from lines NE SW SE
Lease Owner Cities Service Oil Company
Lease Name Eonrardy Well No. 4
Office Address Box 144, Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil Well
Date well completed December 19, 19 54
Application for plugging filed May 15, 19 57
Application for plugging approved May 16, 19 57
Plugging commenced May 24, 19 57
Plugging completed June 1, 19 57
Reason for abandonment of well or producing formation Formation depleted.

If a producing well is abandoned, date of last production April 29, 19 57
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives
Producing formation Viola Depth to top 4491 Bottom 4521 Total Depth of Well 4521 Feet
Show depth and thickness of all water, oil and gas formations. P. B. T. D. 4506'

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	325'	None
				5-1/2"	4521'	3427'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

4506-4480', river sand.
4480-4440', 5 sacks cement.
4440- 300', heavy mud.
300- 230', rock bridge and 20 sacks cement.
230- 30', heavy mud.
30' to base of cellar, rock bridge and 10 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION

6-8-57

CONSERVATION DIVISION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Wilson, Inc. - J. L. King, Operator
Address Stafford, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
V. M. Conover (employee of owner) or (owner/operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) V. M. Conover
Box 144, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 7th day of June 19 57

W. G. Smith
Notary Public.

My commission expires March 12, 1959.

PLUGGING
FILED SEC. 11 T. 29 R. 9W
BOOK PAGE 13 LINE 6

WELL RECORD

Company Cities Service Oil Co. Well No. 4 Farm Conrardy
 Location 990' North and 990' East of S/4 Cor. Sec. 11 T. 29 R. 9W
 Elevation 1706 (1703 Gr.) County Kingman State Kansas
 Drlg. Comm. December 4, 1954 Contractor Barbour Drilling Company
 Drlg. Comp. December 19, 1954 Acid None
 T. D. 4521' Initial Prod. Physical Potential: 86 oil, no water, 24 hrs. (1-5-55)
 P. B. T. D. 4506'

CASING RECORD:

8-5/8" @ 325' cas. 225 wt cement
 5-1/2" @ 4521' cas. 150 wt cement

FORMATION RECORD:

soil & sand	0-110
red bed	190
shale & shells	1360
anhydrite	1360
shale & shells	1420
lime & shale	2375
shale & shells	2510
shale	2690
shale & lime	3175
lime	3310
lime, shale & sand	3450
shale & lime	3578
lime	3635
lime & shale	3680
lime	3914
lime & shale	4200
shale & lime	4212
cherty lime	4270
lime	4289
lime & shale	4327
shale	4380
shale & lime	4440
lime & shale	4478
shale & lime	4500
cherty lime	4522

4522 RTD = 4521 SLM

Corr. Lansing	3555'
Corr. Mississippi	4210'
Corr. Kinderhook	4314'
Corr. Viola	4491'
Penetration	30'
Total Depth	4521'

Drilled cement to 4506 S. L. M.

Perf. 16 shots 4491-95; flowing in 3 1/2 hrs.

SYFO:	330'	0°
	500'	1°
	1000'	1°
	1500'	2°
	2000'	2°
	2500'	1°
	3000'	1°
	3500'	1°
	4000'	1°

RECEIVED
 STATE CORPORATION COMMISSION
 MAY 16 1957
 CONSERVATION DIVISION
 Wichita, Kansas

PLUGGING

FILE SEC. 11 T. 29 R. 9W
 BOOK PAGE 13 LINE 6