

15-095-00548-00-00


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Flat

Kingman County, Sec. 11 Twp. 29 Rge. 9W (E) (W)  
Location as "NE/CNW/SW" or footage from lines N/2 SW SE  
Lease Owner Conrardy Joint Venture c/o C. E. Ridley  
Lease Name Conrardy Well No. 3  
Office Address Box 484 Great Bend, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Oil  
Date well completed 19\_\_  
Application for plugging filed 19\_\_  
Application for plugging approved 19\_\_  
Plugging commenced 19\_\_  
Plugging completed March 1, 1961  
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Fred Hampel  
Producing formation Depth to top Bottom Total Depth of Well 4506' Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

T.D. 4506' - S. P. 8 5/8" - 145' Cwc - 5 1/2" - 4500' - 100 sacks cement  
Bottom, sand to 4480' - 4 sacks cement  
Water plug at 300', bailed fluid to 300'  
10' R. B. at 300' - 15 sacks cement - mud to 140'  
R. B. 10 sacks cement.  
10 R. B. - 300' - 15 sacks cement  
R. B. - 140' - 10 sacks cement  
R. B. - 30' - 10 sacks cement

RECEIVED  
STATE CORPORATION COMMISSION  
WAR 25 1966  
Conservation Division  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Southwest Casing Pulling Company  
Address Box 364 Great Bend, Kansas  
3-25-66

STATE OF Kansas, COUNTY OF Barton, ss:  
Sidney D. Miller - President (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Sidney D. Miller President  
Great Bend, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 24 day of March, 1966

My commission expires Feb. 28, 1968

Wanda C. Spencer  
Notary Public.

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY

508 East Murdock,

Wichita, Kansas


ORIGINAL

Company- AURORA GASOLINE  
Farm- Conrady No. 3

SEC. 11 T. 29 R. 9W  
C N/2 SE SE

Total Depth. 4509'  
Comm. 1-1-56 Comp. 1-6-56  
Shot or Treated.  
Contractor.  
Issued. 3-18-61

County Kingman  
KANSAS



CASING:  
8" 145'  
5" 4506'

Elevation. 1703'

Production. 124 BOPD

Figures Indicate Bottom of Formations.

COMPLETE DRILLERS LOG NOT AVAILABLE

TOPS: SCOUT	
Lansing	3575
Mississippi	4212
Kinderhook	4330
Viola	4504
Total Depth 4509	

RECEIVED  
STATE CORPORATION COMMISSION

JUL 16 1964

CONSERVATION DIVISION  
Wichita, Kansas