


15-095-00541-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217
NORTH



Locate well correctly on above Section Plat

Kingman County, Sec. 11 Twp. 29. Rge. (E) 9 (W)
Location as "NE/CNWSW" or footage from lines 330'N, 1650'E
Lease Owner Cities Service Oil Company
Lease Name Amsden "A" Well No. 1
Office Address 209 E. William, 710 Sutton Place Bldg., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Gas
Date well completed 8-3 19 54
Application for plugging filed 3-1 19 73
Application for plugging approved 3-1 19 73
Plugging commenced 3-5 19 73
Plugging completed 3-6 19 73
Reason for abandonment of well or producing formation Depleted
If a producing well is abandoned, date of last production 12-11 19 72
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well G. R. Biberstein
Producing formation Indian Cave Depth to top 2376 Bottom 2378 Total Depth of Well 4488 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TD	SIZE	PUT IN	PULLED OUT
				8 5/8"	339'	None
				5 1/2"	4488'	2005.93'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

MI csg. PU. SLM 2419 TD; 2419-2320' sand; 2320-2280' 5 sx cement. Shot off 5 1/2 csg. at 1998'. Pulled 65 its. 5 1/2" OD, 14# csg. 2005.93'; 1998-250' by mud; 250-240' rock bridge; 240-base cellar - 4 yards; Redi-mix cement. P&A complete 3-6-73

4-13-73

RECEIVED
STATE CORPORATION COMMISSION

APR 13 1973


CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Southwest Casing Pulling Co.
Address Box 364, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
W. J. Devaney (employee of owner) or (owner) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. J. Devaney
209 E. William, 710 Sutton Place Bldg., Wichita
(Address) Kansas 67202



Subscribed and sworn to before me this 11 day of April, 19 73

Dean Caldwell
Notary Public.

10-16-73

WELL RECORD

Company Cities Service Oil Company Well No. Farm Amesden
 Location 330' North and 1650' East of SW Cor. Sec. 11 T. 29 R. 9W
 Elevation 1685 (1682 Cr.) County Kingman State Kansas
 Drlg. Comm. July 18, 1954 Contractor Barbour Drilling Company
 Drlg. Comp. August 3, 1954 Acid 500 gals. 8-10-54
 T.D. 4488' Initial Prod. B. H. P. Gauge Potential: 1496 oil, no water, 24 hrs.
 P.B.T.D. 4479' (8-31-54)

CASING RECORD:

8-5/8" @ 339' cem. 225 sx cement
 5-1/2" @ 4488' cem. 150 sx cement

FORMATION RECORD:

clay & sand	0-50
sand	100
red bed	340
red bed, shale & shells	720
shale & shells	1520
anhydrite	1535
shale, salt & shells	1715
lime & shale	2330
shale	2655
lime & shale	2960
shale & lime	3030
lime & shale	3180
shale	3200
lime	3270
shale & lime	3350
lime & sand	3430
broken lime	3445
shale	3515
shale & lime	3590
lime	3990
lime & shale	4060
lime	4095
lime & shale	4194
cherty lime	4295
shale	4335
lime	4375
shale	4459
chert & lime	4469
lime	4488

4488 RTD = 4488 SIM

Lansing	3542'
Mississippi	4184'
Kindorhook	4290'
Viola	4458'
Penetration	30'
Total Depth	4488'

Drilled cement to 4479 S.L.M.

Perf. 49 shots 4458-70.

344' oil in 20 mins.
 535' oil in 30 mins.
 1684' oil in 1 hr. 55 mins.
 1863' oil in 2 hrs. 25 mins.

SYFO:	300'	0°
	500'	0°
	1000'	0°
	1500'	1°
	2000'	0°
	2500'	1°
	3000'	0°
	3500'	0°
	4000'	0°

RECEIVED
 STATE CORPORATION COMMISSION

MAR 1 1973

CONSERVATION DIVISION
 Wichita, Kansas