

15-097-30112-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION
Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Form CP-4

WELL PLUGGING RECORD

NORTH

Locate well correctly on above
Section Plat

Kiowa County. Sec. 14 Twp. 29 Rge. 16 (E) (W) x
Location as "NE/CNW/SW" or footage from lines C of SE NW
Lease Owner Eason Oil Co.
Lease Name Scott Well No. #1
Office Address Box 18755, Oklahoma City, Oklahoma
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed 19
Application for plugging filed 10-26-65 19
Application for plugging approved 19
Plugging commenced 10-26-65 19
Plugging completed 10-30-65 19
Reason for abandonment of well or producing formation
If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced?

Name of Conservation Agent who supervised plugging of this well
Producing formation Depth to top Bottom Total Depth of Well 4780' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS				CASING RECORD		
FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Mudded hole to 240', set 10' rock bridge. Mixed and ran 2 sacks cement thru dump bailer. Mixed and ran 2 sacks Calseal thru dump bailer. Bailed hole down dry. Mixed and ran 50 sacks cement thru dump bailer. Mudded hole to 40' - set 10' rock bridge. Mixed and dumped 30 sacks cement to base of cellar.

RECEIVED
STATE CORPORATION COMMISSION
NOV 2 1965
CONSERVATION DIVISION
Wichita, Kansas

11-2-65

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Southwest Casing Pulling Co., Inc.
Address Box 364, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
Southwest Casing Pulling Co., Inc. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) D. C. Spencer
Box 364, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 1 day of November, 1965

My commission expires 24 October 1968
Sidney D. Miller
Notary Public.

GABBERT-JONES, INC.
WICHITA, KANSAS
DRILLERS' WELL-LOG

SCOTT #1
 C SE NW SECTION 14-29S-16W
 KIOWA COUNTY, KANSAS

COMMENCED: OCTOBER 4, 1965
 COMPLETED: OCTOBER 23, 1965

OPERATOR - EASON OIL COMPANY

DEPTH	FORMATION	REMARKS
From To		
0 30	SURFACE CLAY	
30 120	SAND	
120 250	SHALE	RAN 250' OF 13-3/8" CASING, SET @ 250' w/250 SACKS CEMENT.
250 499	SHALE	
499 945	RED BED	
945 960	ANHYDRITE	
960 1915	SHALE AND SHELLS	
1915 2114	SHALE AND LIME	
2114 2400	LIME	RAN 2400' OF 8-5/8" CASING, SET @ 2400' w/125 SACKS CEMENT.
2400 2595	LIME	
2595 3825	LIME AND SHALE	
3825 4090	LIME, SHALE AND SAND	
4090 4500	LIME	
4500 4600	LIME AND SHALE	
4600 4650	LIME	
4650 4730	CORE	
4730 4733	LIME	
4733 4780	CHERT AND LIME	
4780 TO		DRY AND ABANDONED.

RECEIVED
 STATE CORPORATION COMMISSION

NOV 18 1965

CONSERVATION DIVISION

I, E. E. HALL, CERTIFY THIS IS A CORRECT COPY OF THE DRILLERS' LOG FOR THE WELL DRILLED IN THE C SE NW SECTION 14-29S-16W, KIOWA COUNTY, KANSAS, TO THE BEST OF MY KNOWLEDGE AND BELIEF.

E. E. Hall
 E. E. HALL

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

BEFORE ME, THE UNDERSIGNED, A NOTARY PUBLIC WITHIN AND FOR SAID COUNTY AND STATE, ON THIS 27TH DAY OF OCTOBER, 1965, PERSONALLY APPEARED E. E. HALL, TO ME PERSONALLY KNOWN TO BE THE IDENTICAL PERSON WHO EXECUTED THE WITHIN AND FOREGOING INSTRUMENT AND ACKNOWLEDGED TO ME THAT HE EXECUTED THE SAME AS HIS FREE AND VOLUNTARY ACT AND DEED FOR THE USES AND PURPOSES THEREIN SET FORTH.

IN WITNESS WHEREOF, I HAVE HEREUNTO SET MY HAND AND OFFICIAL SEAL THE DAY AND YEAR LAST ABOVE WRITTEN.

Barbara J. Layton
 BARBARA J. LAYTON, NOTARY PUBLIC

MY COMMISSION EXPIRES FEBRUARY 1, 1968.