

NOV 28 1962

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
11 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

Kiowa County, Sec. 19 Twp. 29S Rge. 16W (X) (W)

Location as "NE/CNW/SWK" or footage from lines SE NW

Lease Owner Graybol Oil Corporation

Lease Name Estate Well No. 1

Office Address 2200 National Bank of Tulsa Bldg., Tulsa, Oklahoma

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed November 18 19 62

Application for plugging filed November 18 19 62

Application for plugging approved November 18 19 62


Plugging commenced November 19 19 62

Plugging completed November 19 19 62

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production \_\_\_\_\_ 19 \_\_\_\_\_

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Herman Justus

Producing formation None Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4791 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
<u>Douglas Sand</u>	<u>Salt Water</u>	<u>4019</u>	<u>4044</u>	<u>8 5/8"</u>	<u>308'</u>	<u>None</u>
<u>Lansing Lime</u>	<u>Salt Water</u>	<u>4159</u>	<u>4543</u>			
<u>Mississippi Chat</u>	<u>Impermeable</u>	<u>4715</u>	<u>4727</u>			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled hole with heavy mud-laden fluid. Pushed plug to 200'. Cemented with 25 sacks Portland Cement. Plugged top 40' of surface casing with ten sacks of Portland Cement, two sacks of Portland cement in rat hole.

(if additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Graybol Oil Corporation

Address 2200 National Bank of Tulsa Bldg., Tulsa, Oklahoma

STATE OF OKLAHOMA, COUNTY OF Tulsa, ss.

Lyman C. Dennis (employee of owner) or (~~owner or operator~~) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Lyman C. Dennis

Tulsa, Oklahoma  
(Address)

SUBSCRIBED AND SWORN to before me this 27th day of November, 19 62

My commission expires October 8, 1966

Law Carrigan  
Notary Public.

GRAYBOL OIL CORPORATION

Kiowa County, Kansas

No. 1 Estate

SE NW Section 19-29S-16W

Contractor: Company Tools

Elev: 2057' K.B. 2057' D.F. 2051' G.L.

Commenced: October 30, 1962

Completed: November 18, 1962

Production: Dry and Abandoned

CASING RECORD

308' of 8 5/8" casing cemented with 210 sacks cement.

DEPTH	FORMATION	WELEX ELECTRIC LOG TOPS:
0-40	Sand	Anhydrite 965
40-310	Shale and shells	Topeka 3512
310-964	Shale and red bed	Heebner 3982
964-978	Anhydrite	Toronto 4002
978-1220	Shale and Lime	Douglas 4021
1220-1930	Shale and Shells	Brown Lime 4140
1930-2103	Shale	Lansing 4159
2103-2135	Lime and Shale	Mississippi Chat 4716
2135-2174	Lime	Kinderhook 4772
2174-2239	Lime and Shale Streaks	Viola 4788
2239-2315	Lime and Shale	Welex Total Depth 4792
2315-2476	Lime	
2476-2722	Lime and Shale	
2722-2795	Lime and Shale Streaks	
2795-3017	Lime and Shale	
3017-3215	Shale and Lime	
3215-3295	Lime and Shale	
3295-3399	Shale and Lime	
3399-3458	Lime and Shale	
3458-3695	Shale and Lime	
3695-3764	Lime, Shale & Chert	
3764-3807	Lime and Shale	
3807-3851	Lime and Shale Streaks	
3851-4090	Lime and Shale	
4090-4136	Shale and Lime	
4136-4144	Lime	
4144-4155	Shale	
4155-4170	Lime	
4170-4270	Lime and Shale	
4270-4315	Lime	
4315-4415	Lime and Shale	
4415-4455	Lime	
4455-4530	Lime and Shale	
4530-4570	Lime and Shale Streaks	
4570-4625	Lime and Shale	
4625-4674	Lime, Sand and Shale	
4674-4711	Lime and Shale	
4711-4721	Chat	
4721-4725	Lime	
4725-4754	Lime and Shale	
4754-4791	Lime, Shale & Chert	

Driller's T. D. 4791'

I hereby certify that the above is a true and correct log of the above captioned well as taken directly from the daily drilling reports.

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 21 1962  
CONSERVATION DIVISION  
Wichita, Kansas

GRAYBOL OIL CORPORATION

By: Lyman C. Dennis  
Lyman C. Dennis, Geologist

STATE OF OKLAHOMA

COUNTY OF TULSA

Subscribed and sworn to this 20th day of November, 1962.

My commission expires: October 8, 1966

Jaw Creegan  
NOTARY PUBLIC