

15-097-10038-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION


Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

WELL PLUGGING RECORD

KIOWA County. Sec. 19 Twp. 29S Rge. (E) 16W (W)

Location as "NE/CNW/SW" or footage from lines SW NE
Lease Owner GRAYBOL OIL CORPORATION
Lease Name BUNDREN Well No. 1
Office Address NATIONAL BANK OF TULSA - TULSA, OKLAHOMA
Character of Well (completed as Oil, Gas or Dry Hole) OIL
Date well completed OCTOBER 27 19 62
Application for plugging filed FEBRUARY 29 19 72
Application for plugging approved 19
Plugging commenced MARCH 3 19 72
Plugging completed MARCH 15 19 72
Reason for abandonment of well or producing formation DEPLETED



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well RUSSELL BIBERSTEIN
Producing formation Depth to top Bottom Total Depth of Well 4797 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	305'	NONE
				4 1/2"	4789'	2383.63'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

4797' - 4700' - SAND
4700' - 4652' - 4 SACKS CEMENT
4652' - BASE - PUMPED 100 SACKS CEMENT, 15 SACKS OF GEL AND 2 SACKS OF HULLS.

RECEIVED
STATE CORPORATION COMMISSION
MAR 31 1972
CONSERVATION DIVISION
Wichita, Kansas

3-31-72

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor SANTA-FE PIPE & SUPPLY, INC.
Address BOX 562 - GREAT BEND, KANSAS 67530

STATE OF KANSAS, COUNTY OF BARTON, ss.
T. L. NUTT (employee of owner) or (owner/contractor) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *T. L. Nutt*

BOX 562 - GREAT BEND, KANSAS 67530
(Address)

Subscribed and Sworn to before me this 28th day of March, 19 72

My commission expires July 31, 1974

Mary M. Guesnier
Mary M. Guesnier Notary Public.

FILE COPY

GRAYBOL OIL CORPORATION

Kiowa County, Kansas

No. 1 Bundren SW NE

Section 19-29S-16W

Contractor: Company Tools

Elev: 2077' K.B. 2077' D.F.
2071' G.L.

Commenced: October 10, 1962

Completed: October 27, 1962

Production: Not yet tested.

CASING RECORD

8 5/8" set at 305' with 225 sacks cement. Not pulled.
4 1/2" set at 4789' with 80 sacks cement. Not pulled.

DEPTH	FORMATION	WELEX ELECTRIC LOG TOPS:
0-60	Sand and Clay	Stone Corral Anhydrite 978
60-250	Shale	Topeka Limestone 3531
250-310	Shale and Sand	Hoebner Shale 4003
310-978	Shale and Red Bed	Toronto Limestone 4023
978-1000	Anhydrite	Douglas Sand 4044
1000-1360	Shale	Brown Lime 4161
1360-1680	Sandy Shale	Lansing Limestone 4180
1680-2075	Shale and Shells	Base of Kansas City 4564
2075-2120	Shale and Lime	Marmaton Limestone 4562
2120-2212	Lime	Mississippi Chat 4732
2212-2314	Lime and Shale Streaks	
2314-2454	Lime	
2454-2546	Lime and Shale	
2546-2585	Lime	
2585-2603	Shale	
2603-2850	Shale and Lime	
2850-3003	Shale	
3003-3073	Lime and Shale	
3073-3127	Shale and Lime	
3127-3382	Shale and Lime Streaks	
3382-3624	Shale and Lime	
3624-3842	Lime and Shale	
3842-3873	Lime	
3873-3942	Lime and Shale	
3942-4021	Lime	
4021-4087	Lime and Shale	
4087-4134	Lime and Shale Streaks	
4134-4250	Lime and Shale	
4250-4271	Lime	
4271-4324	Lime and Shale	
4324-4383	Lime	
4383-4419	Chalky Lime	
4419-4555	Lime	
4555-4640	Lime and Shale	
4640-4695	Lime	
4695-4735	Lime and Shale	
4735-4745	Chat	
4745-4752	Lime	
4752-4781	Lime and Shale	
4781-4797	Lime	
Driller's T. D. 4797'		Welex T. D. 4794'

RECEIVED
STATE CORPORATION COMMISSION
MAR 2 1972
CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above is a true and correct log of the above-captioned well as taken directly from the daily drilling reports.

GRAYBOL OIL CORPORATION

By: Lyman C. Dennis
Lyman C. Dennis, Geologist

STATE OF OKLAHOMA

COUNTY OF TULSA

Subscribed and sworn to this 1st day of November, 1962.

My commission expires: October 8, 1966

John Corrigan
NOTARY PUBLIC