

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
301 S. Market, Room 2078  
Wichita, KS 67202

WELL PLUGGING RECORD  
K.A.R.-02-3-117

API NUMBER 15-007-21,925-00-00

LEASE NAME Baldwin

WELL NUMBER 2-35

4470 Ft. from S Section Line

4620 Ft. from E Section Line

SEC. 35 TWP. 30S RGE. 12W (E) or (W)

COUNTY Barber

Date Well Completed \_\_\_\_\_

Plugging Commenced 1-3-01

Plugging Completed 1-8-02

LEASE OPERATOR VESS OIL CORPORATION

ADDRESS 8100 E. 22nd. St. N. Bldg #3000 Wichita, Kansas 67226

PHONE# (316) 682-1537 OPERATORS LICENSE NO. \_\_\_\_\_

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

This plugging proposal was approved on \_\_\_\_\_ (date)

by Steve Pfeifer (KCC District Agent's Name).

Is ACO-1 filed? \_\_\_\_\_ If not, is well log attached? \_\_\_\_\_

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 4680'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	351'	None
				4-1/2"	4516'	2820'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each section. Set bridge plug @3940', dumped 2 sx. cement on top. Shot pipe @3000' & 2820', pulled casing. Pumped 300# hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100# hulls, 8-5/8" wiper plug and 100 sx. cement, 60/40 pos. 6% gel down 8-5/8" surface. Plugging Complete.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 467 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Vess Oil Corporation

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and statements, and matters herein contained and the log of the above-described well as filed to the same are true and correct, so help me God.

(Signature) [Signature]

(Address) P. O. Box 467 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 17th day of January 2002

[Signature]  
Notary Public

My Commission Expires: \_\_\_\_\_

