

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-151-21,446 <sup>00-00</sup>

LEASE NAME Kennedy

WELL NUMBER 3-30

SPOT LOCATION NW SW SE

SEC. 30 TWP. 29 RGE. 12 ~~30~~ (W)

COUNTY Pratt

Date Well Completed 7-7-84  
9:30 PM,

Plugging Commenced 7-7-84

Plugging Completed 11:15 PM  
7-7-84

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR F. G. Holl  
ADDRESS 6427 East Kellogg  
Wichita, Kansas 67207

PHONE # (316) 684-8481 OPERATORS LICENSE NO. 5056'

Character of Well D&A  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? District No. 1

Is ACO-1 filed?                      If not, is well log attached? Yes

Producing formation                      Depth to top                      bottom                      T.D. 4770'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				10 3/4"	268'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from    feet to    feet each set.

Filled hole with heavy mud. Heavy mud and 50 sacks at 1070';  
heavy mud and 50 sacks at 320'; heavy mud, 1/2 sack hulls, plug and 10 sasks at 40'.  
15 sacks in rathole; 10 sacks in mousthold and 5 sacks in water well. Used 60/40  
Pozmix with 2% gel.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sterling Drilling Company License No. 5142  
Address P. O. Box 129, Sterling, Kansas 67579

RECEIVED  
STATE CORPORATION COMMISSION

STATE OF KANSAS COUNTY OF RICE, ss.

F. A. Wuellner (employee of operator) or  
(operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) F. A. Wuellner  
F. A. Wuellner, Secretary  
(Address) P. O. Box 129, Sterling, Kansas  
67579

SUBSCRIBED AND SWORN TO before me this 9th day of July, 19 84.

Agnes D. Wurst  
Agnes D. Wurst, Notary Public

My Commission expires: 4-6-85



# STERLING DRILLING CO.

BOX 129

STERLING, KANSAS 67579

WELL LOG ----- KENNEDY #3-30

Located: NW SW SE, Section 30-29S-12W, Pratt County, Kansas

OWNER: F. G. Holl

ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: June 27, 1984

COMPLETED: July 7, 1984

TOTAL DEPTH: 4770'

## LOG

0 - 190 Sand

190 - 270 Red Bed

270 - 1570 Shale

1570 - 4770 Lime and Shale

## CASING RECORD

Ran 6 joints 10 3/4" OD casing. 255.70'  
pipe set at 268' K.B. Cemented with 225  
sacks Common, 2% gel and 3% cc. Plug down  
at 12:15 AM, 6-28-84, by HowcD.

Plugged.

Deviation Surveys: 1° at 2145'  
1 1/4° at 4502'

RECEIVED  
STATE CORPORATION COMMISSION

JUL 12 1984

CONSERVATION DIVISION  
Wichita, Kansas