

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-151-21,593 <sup>06-00</sup>

LEASE NAME Hirt #1-30

WELL NUMBER 1-30

SPOT LOCATION NE NE NE

SEC. 30 TWP. 29 RGE. 12 (E) (W)

COUNTY Pratt

Date Well Completed 5-16-85

5:00 PM

Plugging Commenced 5-16-85

6:45 PM

Plugging Completed 5-16-85

TYPE OR PRINT

NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR F. G. Holl

6427 East Kellogg

ADDRESS Wichita, Kansas 67207

PHONE # (316) 684-8481 OPERATORS LICENSE NO. 5056

Character of Well D&A  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? District No. 1

Is ACO-1 filed?                      If not, is well log attached? Yes

Producing formation                      Depth to top                      bottom                      T.D. 4795'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	267'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from    feet to    feet each set.

Filled hole with heavy mud plugged thorough open ended drill pipe, circ. before plugged, 50 sacks at 820'; 50 sacks at 280'; 1/2 sack hulls, plug and 10 sacks at 40', circ. 15 sacks in rathole with joint of pipe. Used 60/40 Pozmix, 2% gel (total 4%) plus 3% cc.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sterling Drilling Company License No. 5142

Address P. O. Box 129, Sterling, Kansas 67579

STATE OF KANSAS COUNTY OF RICE, ss. STATE CORPORATION COMMISSION

RECEIVED  
5-21-85  
MAY 21 1985

F. A. Wuellner (employee of operator) or  
(operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) F. A. Wuellner

(Address) F. A. Wuellner, Secretary  
P. O. Box 129

Sterling, Kansas 67579

SUBSCRIBED AND SWORN TO before me this 17 day of May, 19 85.



Agnes D. Wurst  
Notary Public

My Commission expires: 4-6-89

# STERLING DRILLING CO.

BOX 129

STERLING, KANSAS 67579

WELL LOG ----- HIRT #1-30  
Located: NE NE NE, Section 30-29S-12W, Pratt County, Kansas

OWNER: F. G. Holl

ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: May 7, 1985

COMPLETED: May 16, 1985

TOTAL DEPTH: 4795'

## LOG

0 - 190 Sand and Shale  
190 - 270 Shale and Red Bed  
270 - 1060 Shale and Sand  
1060 - 1770 Shale  
1770 - 4795 Lime and Shale

## CASING RECORD

Ran 6 joints new 8 5/8", 23# casing.  
25508' pipe set at 267' K.B. Cemented  
with 210 sacks 60/40 Pozmix plus 3% cc.  
Plug down at 2:00 PM, 5-7-85, by Howco.  
  
Plugged.

Deviation Surveys: 1° at 1936'

1/2° at 4391'  
RECEIVED  
STATE CORPORATION COMMISSION

MAY 21 1985

CONSERVATION DIVISION  
Wichita, Kansas