

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Pratt County. Sec. 32 Twp. 28 Rge. 14W (E) (W)
Location as "NE/CNW/SW" or footage from lines C NE NE

Lease Owner Crescent Oil & Gas Corporation

Lease Name Davis Well No. 1

Office Address Box 412, Tulsa, Oklahoma

Character of Well (completed as Oil, Gas or Dry Hole) D & A

Date well completed 5/30 1963

Application for plugging filed 5/29 1963

Application for plugging approved 5/29 1963


Plugging commenced 5/29 1963

Plugging completed 5/30 1963

Reason for abandonment of well or producing formation No commercial quantities of oil or gas encountered

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Archie Elving

Producing formation None Depth to top Bottom Total Depth of Well 4800 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface	Water			10-3/4"	345'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Mud was introduced into the hole to a depth of 310 feet where a plug was set and cemented with 14 sacks cement. Top of cement at 288 feet. No other plugs were set because the landowner is going to perforate the surface casing for irrigation well.

RECEIVED
STATE CORPORATION COMMISSION

JUN 10 1963

6-10-63

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Tomlinson-Kathol, Inc.

Address 1125 Wichita, Plaza, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.

Richard C. Davis (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]

1125 Wichita Plaza, Wichita, Kansas

(Address)

SUBSCRIBED AND SWORN TO before me this 10th day of June, 1963

My commission expires 1/19/65

[Signature]
Esther Lamone
Notary Public.



DRILLERS LOG
 CRESCENT OIL & GAS CORP.
 # 1 DAVIS
 C NE NE, SEC. 32-28S-14W
 PRATT COUNTY, KANSAS


Contractor - Tomlinson-Kathol, Inc.

Commenced: 5/13/63
 Completed: 5/29/63
 Elevation 2039 KB

To	From	Description	Remarks
0	60	Clay	
60	98	Sand	
98	123	Clay	
123	270	Gravel	
270	305	Sand	
305	354	Shale, Red Bed	345' 10-3/4" surface casing
354	730	Shale, Sand	w/250 sacks cement
730	1034	Shale, rathole	
1034	1995	Shale	
1995	2055	Shale - Lime streaks	
2055	2170	Shale & Lime	
2170	2445	Lime	
2445	2555	Shale & Lime	
2555	2895	Lime	
2895	3030	Lime, Shale	
3030	3225	Shale	
3225	3320	Shale - Lime Streaks	
3320	3390	Lime - Shale	
3390	3664	Shale - Lime	
3664	3742	Shale	
3742	3821	Lime & Shale	
3821	3978	Shale - Lime	
3978	4086	Lime - Shale	
4086	4537	Lime	
4537	4563	Lime & Chert	
4563	4604	Lime - Shale - Chert	
4604	4628	Lime & Chert	
4628	4652	Shale	
4652	4680	Chert - Shale	
4680	4703	Lime, chert	
4703	4743	Sand, Dolomite	
4743	4776	Shale - Lime - Chert	
4776	4800	Arbuckle	
4800		Rotary Total Depth	

RECEIVED
 STATE CORPORATION COMMISSION
 JUN 10 1963
 CONSERVATION DIVISION
 Wichita, Kansas

I certify to the best of my knowledge and belief, the above represents a true and accurate driller's log record of the captioned well.


 Richard C. Davis

STATE OF KANSAS

SS:

COUNTY OF SEDGWICK

Subscribed and sworn to before me this 4th day of June, 1963.


 Notary Public, Esther Lamone

My Commission Expires: 1/19/65