

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

WELL PLUGGING RECORD

API NUMBER 15151-20715-00-00

LEASE NAME Eubank

TYPE OR PRINT
PLEASE FILL OUT COMPLETELY
AND MAKE REQUIRED AFFIDAVIT.

WELL NUMBER #1

SPOT LOCATION C SE SW

SEC 30 TWP 28S RGE 14 (E) OR (W)

COUNTY Pratt

DATE WELL COMPLETED 2-25-80

PLUGGING COMMENCED 12-17-83

PLUGGING COMPLETED 1-3-84

LEASE OPERATOR Hummon Oil Company

ADDRESS Suite 400 - One Main Place - Wichita, KS 67202

PHONE # (316) 263-8521 OPERATORS LICENSE NO. 5050

CHARACTER OF WELL
(OIL, GAS, D&A, SWD, INPUT, WATER SUPPLY WELL)

DID YOU NOTIFY THE KCC/KDHE JOINT DISTRICT OFFICE PRIOR TO PLUGGING THIS WELL? Yes

WHICH KCC/KDHE JOINT OFFICE DID YOU NOTIFY? Lacey and Luthi

IS ACO-1 FILED? _____ IF NOT, IS WELL LOG ATTACHED? _____

PRODUCING FORMATION _____ DEPTH TO TOP _____ BOTTOM T.D. 4707

SHOW DEPTH AND THICKNESS OF ALL WATER, OIL AND GAS FORMATIONS.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION.	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	378	None
				4 1/2	4624	1700

DESCRIBE IN DETAIL THE MANNER IN WHICH THE WELL WAS PLUGGED, INDICATING WHERE THE MUD FLUID WAS PLACED AND THE METHOD OR METHODS USED IN INTRODUCING IT INTO THE HOLE. IF CEMENT OR OTHER PLUGS WERE USED STATE THE CHARACTER OF SAME AND DEPTH PLACED, FROM FEET TO FEET EACH SET. Plugged back at 4584. Sand from 4584 to 4480. 4 sacks cement from 4480 to 4450. Pulled 1700 4 1/2".

3 sacks hulls - 15 jell - 50 cement - 10 jell - 1 hull - Pulled. 100 sacks 60-40 2%. 3% C. C.

Zimmerman and lacey on location

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

NAME OF PLUGGING CONTRACTOR Clarke Corporation LICENSE No. 5105

ADDRESS P O Box 187 - Medicine Lodge, KS 67104

STATE OF _____ COUNTY OF _____, ss.

(EMPLOYEE OF OPERATOR) OR (OPERATOR) OF ABOVE-DESCRIBED WELL, BEING FIRST DULY SWORN ON OATH, SAYS: THAT I HAVE KNOWLEDGE OF THE FACTS, STATEMENTS, AND MATTERS HEREIN CONTAINED AND THE LOG OF THE ABOVE-DESCRIBED WELL AS FILED THAT THE SAME ARE TRUE AND CORRECT, SO HELP ME GOD.

(SIGNATURE) [Signature]

(ADDRESS) _____

SUBSCRIBED AND SWORN TO BEFORE ME THIS 13 DAY OF January, 1984

Pamela Ricker
NOTARY PUBLIC

MY COMMISSION EXPIRES: 10-11-87

RECEIVED
STATE CORPORATION COMMISSION

FORM CP-4
REVISED 06-83

JAN 16 1984

1-16-84

CONSERVATION
Wichita, Kansas

Hummon & Ropfogel
400 One Main Place
Wichita, Kansas 67202

Eubank #1
C SE SW Sec. 30-28S-14W
Pratt County, Kansas

Contractor: D. R. Lauck Oil Company, Inc.
221 S. Broadway, Suite 400
Wichita, Kansas 67202

Commenced: February 15, 1980
Completed: February 25, 1980

Drillers Log

Shale	90
Sand	200
Red Bed	893
Anhydrite	904
Shale	2135
Shale & Shells	3715
Shale & Lime	4155
Lime	4707 RTD

IMPORTANT
 Kans. Geo. Survey request
 samples on this well.

KANSAS DRILLERS LOG

S. 30 T. 28 R. 14 ^W

API No. 15 — 151 — 20,715 - 80-40
 County Number


Loc. C SE SW

Operator
Hummon Corp.

County PRATT

Address
400 One Main Pl., Wichita, KS 67202

Well No. 1 Lease Name
Eubank



Footage Location
660 feet from ~~330~~ (S) line 660 feet from (E) ~~330~~ line

Principal Contractor D. R. Lauck Oil Company Geologist John Carnes

Spud Date 2/15/80 Total Depth 4707 P.B.T.D.

Elev.: Gr. 2029

Date Completed 2/25/80 Oil Purchaser ?

DF 2031 KB 2034

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/4	8-5/8	28#	378	Common	275	2%gel 3%cc
Production	7-7/8"	4 1/4	10.5#	4624	60-40 Poz	125	10% salt, 6/10 of 1% Halad, 3/4 of 1% CFR2, 2% gel.

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			4 holes	hydrojet	4534'

Size	Setting depth	Packer set at
2"	4527.20	

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
500 gal 15% MCA & Nitrogen	4534'
Foam frac w/ 100 sx 20-40 sand 20,000 gal foam	4534'

INITIAL PRODUCTION

Date of first production	Producing method (flowing, pumping, gas lift, etc.) <u>flowing</u>		
RATE OF PRODUCTION PER 24 HOURS	Oil <u>70</u> bbls.	Gas <u>400</u> MCF	Water <u> </u> bbls.
Disposition of gas (vented, used on lease or sold)	Producing interval (s) <u>4534</u>		

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on an open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator Hummon Corporation		DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.: oil/gas
Well No. #1	Lease Name Eubank	
S 30 T 28S R 14 ^{XXX} W		

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
DST #1: 4325-4353 OP 30-30-15-40 FP 29-39, SIP 49-39 Rec. 10' mud			Elect. log	
DST #2: 4487-4527 OP 30-45-45-60 Fair blow inc. to strong Rec. 35' drilling mud FP 39-39 SIP 438-564			Heebner Brown LM Lansing B/KC Marm. Miss. Kinderhook RTD 4707 LTD 4711	3856 -1822 4015 -1981 4032 -1998 4404 -2370 4421 -2387 4512 -2478 4530 -2496
DST #3: 4486-4562 OP 30-45-60-90 Weak blow inc. to strong GTS 2 hrs. 15 min. Rec. 124' gas and slightly oil cut mud 372' very heavy gas cut mud SIP 794-991 FP 40-199				

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received	<p align="center"><i>Wilber Berg</i> Signature Wilber Berg</p> <p align="center">Title 3-1-80 Date</p>
---------------	--