

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

PRATT County, Sec. 28 Twp. 28 Rge. 14 (E) W (W)

Location as "NE/CNW/SE/SW" or footage from lines NE, NE, NW
Lease Owner COOPERATIVE REFINERY ASSOCIATION
Lease Name S P I N E S Well No. 1
Office Address BOX 2359--KANSAS CITY 42, MISSOURI
Character of Well (completed as Oil, Gas or Dry Hole) DRY HOLE
Date well completed 8-24 1954
Application for plugging filed 8-24 1954
Application for plugging approved 8-24 1954
Plugging commenced 8-24 1954
Plugging completed 8-25 1954
Reason for abandonment of well or producing formation DRY HOLE

NORTH

	X		

Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well M. A. RIVES
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4680 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	354	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

HOLE WAS FILLED WITH DRILLING MUD TO 300 FEET, HULLS WERE ROLLED IN SACK AND PLACED IN HOLE. HALLIBURTON PLUG WAS PUSHED DOWN 300 FEET WITH DRILL PIPE. 20 SACKS OF CEMENT WERE THEN MIXED AND POURED THROUGH THE DRILL PIPE. HOLE WAS FILLED TO 35 FEET WITH MUD AND 1/3 SACK OF HULLS WERE PUSHED DOWN 35 FEET WITH KELLY. HALLIBURTON PLUG WAS RUN ON WIRE LINE. 10 SACKS OF CEMENT WERE THEN MIXED AND POURED DOWN THE HOLE. PLUGGING COMPLETED @ 1:00 A. M. AUGUST 25, 1954.

RECEIVED
CONSERVATION DIVISION
8-26-54
AUG 27 1954
WICHITA, KANSAS

Name of Plugging Contractor SCHAFFER DRILLING COMPANY
Address BOX 350----PRATT, KANSAS

STATE OF KANSAS COUNTY OF PRATT, ss.
J. E. Selby (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. E. Selby
PRATT, KANSAS
(Address)

SUBSCRIBED AND SWORN TO before me this 25th day of August, 19 54

My commission expires

June 30, 1955.

Maudie B. McBride
Notary Public.

PLUGGING
FILE SEC 28-28-R-14W
BOOK PAGE 39 LINE 13

DRILLER'S LOG
SPINES # 1

COOPERATIVE REFINERY ASSOCIATION, Etal.
PRATT COUNTY, KANSAS

COMMENCED August 4, 1954
COMPLETED August 24, 1954

0-180	Sand & gravel
180-1052	Red Bed & shells
1052-1650	Shale & shells
1650-1680	Anhydrite
1680-1900	Shale & shells
1900-2095	Shale & lime
2095-2260	Lime
2260-2375	Shale & lime
2375-2445	Lime
2445-2565	Shale & lime
2565-2685	Shale & lime shells
2685-2815	Shale & lime
2815-3230	Shale & shells
3230-3380	Shale & lime shells
3380-3390	Shale & lime
3390-3480	Shale & shells
3480-3990	Shale & lime
3990-4316	Lime
4316-4390	Shale & lime
4390-4428	Lime
4428-4450	Shale & chert
4450-4482	Shale & lime
4482-4556	Lime & chert
4556-4608	Coring
4608-4650	Shale & lime
4650-4680	Arbuckle
4680	TOTAL DEPTH


I certify that the above drillers log is true and correct as being taken directly from the daily drilling reports of the Spines #1.

J. E. Selby
J. E. Selby
SCHAFFER DRILLING COMPANY

STATE OF KANSAS: COUNTY OF PRATT: SS:

Subscribed and sworn to before me this 25th day of August, 1954.

My commission expires June 30, 1955.



Maudie B. McBride
Notary Public
STATE CORPORATION COMMISSION
AUG 26 1954
CONSERVATION DIVISION
Wichita, Kansas