


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biffing Building
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Pratt County. Sec. 26 Twp. 28S Rge. 11 (E) 14 (W)

Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines NW NW NW
Lease Owner Iron Drilling Company
Lease Name L. H. Hatfield Well No. 1
Office Address 1206 Philtower Building
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed October 28 19 51
Application for plugging filed October 28 19 51
Application for plugging approved October 28 19 51
Plugging commenced October 28 19 51
Plugging completed October 28 19 51
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well C. D. Stough
Producing formation Depth to top Bottom Total Depth of Well 4645 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8"	188'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from.....feet to.....feet for each plug set.

Hole filled with heavy mud
Bottom plug set at 190 feet and dumped 15 sack cement
Top plug set at 40 feet dumped 10 sack cement & 1 sack hulls

RECEIVED
STATE CORPORATION COMMISSION
NOV-1-1951
CONSERVATION DIVISION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Iron Drilling Company
Address 1206 Philtower Building, Tulsa, Oklahoma

STATE OF Oklahoma, COUNTY OF Tulsa, ss.
Herrick Babcock (employee of owner) or (owner or operator) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Herrick Babcock
1206 Philtower Building, Tulsa, Oklahoma
(Address)

SUBSCRIBED AND SWORN to before me this 31st day of October, 19 51

My commission expires Feb. 28, 1952 Notary Public.

FILED
OCT 28 1951
PAGE 18 LINE 1

DRILLING RECORD

Well L. E. Hatfield No. 1
 Located NW NW NW Sec. 26-28S-14W
 Pratt County, Kansas

Casing Record

188' of 8-5/8" OD Surface Pipe
 cemented with 150 sacks.

Work Commenced 10/8/51
 Drilling Commenced 10/9/51
 Drilling Completed 10/28/51
 Work Completed 10/29/51

No Oil String - Dry Hole

WELL LOG

Sand	0 to 35
Sandy Clay	35 to 180
Red Bed	180 to 660
Red Bed & Shale	660 to 750
Anhydrite & Shells	750 to 800
Red Bed & Shale	800 to 1050
Shale & Shells	1050 to 1385
Shale & Lime Shells	1385 to 1675
Lime & Shale	1675 to 1900
Lime	1900 to 2255
Shale & Lime	2255 to 2345
Lime	2345 to 2505
Lime & Shale	2505 to 2620
Salt & Shale	2620 to 2645
Shale & Lime	2645 to 2812
Shale & Sandy Lime	2812 to 2917
Shale & Lime	2917 to 3260
Lime	3260 to 3460
Lime & Shale	3460 to 3505
Lime	3505 to 3685
Lime & Shale	3685 to 3950
Lime & Chert	3950 to 3994
Lime	3994 to 4350
Cherty Lime & Shale	4350 to 4395
Chert & Conglomerate	4395 to 4430
Cherty Lime	4430 to 4450
Shale & Sandy Lime	4450 to 4465
Cherty Lime & Sand	4465 to 4478
Chert	4478 to 4495
Cherty Lime & Shale	4495 to 4515
Shale & Sand	4515 to 4546
Lime	4546 to 4565
Shale & Lime	4565 to 4645 TD

PLUGGING
 FEB 26 28 R (C)
 BOOK PAGE 124 LINE 1

CERTIFICATION

State of Oklahoma, County of Tulsa, SS

I, Herrick Babcock, Partner of Iron Drilling Company, Certify that the above is a true and correct log of the above described well.

RECEIVED
 STATE COMMISSION
 Signature *Herrick Babcock*
 NOV 1 1951

Subscribed to and Sworn before me this 31st day of October, 1951.

W. H. MICHAL
 DIVISION
W. H. Michal

My commission expires Feb. 28, 1952.