

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-151-21-434-0000

LEASE NAME Cosby

TYPE OR PRINT

NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 1

895 Ft. from Section Line

585 Ft. from L. Section Line

LEASE OPERATOR Raymond M. Gooden Trust

SEC. 1 TWP. 28s RGE. 15 (E) or (W)

ADDRESS 3300 Carlock, Wichita, KS 67202

COUNTY Pratt

PHONE# (316) 838-3670 OPERATORS LICENSE NO. 5501

Date Well Completed _____

Character of Well good

Plugging Commenced 8-9-95

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 8-17-95

The plugging proposal was approved on 8/9/95 (date)

by Richard Lacy (KCC District Agent's Name).

Is ACO-1 filed? X If not, Is well log attached? _____

Producing Formation Miss Depth to Top 4486 Bottom 4506 T.D. 4703

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8	442	None
				5 1/2	4703	Approx 2400'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each section. Sand well back to 4360, dump 5sx cement with dump bailer, stretch and cut pipe at approx. 2400' lay down casing, Allied pump 300 hulls, 10 jel, 50 sx cement, 10 jel, 100 hulls, 8 5/8 wiper plug and 100sx cement, 60/40 POZ, 6% jel

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Clarke Corporation

RECEIVED
STATE CORPORATION COMMISSION
KANSAS No. 5105

Address P.O. Box 187, Medicine Lodge, KS 67104

AUG 28 1995


NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Raymond M. Goodin Trust 8-28-95

STATE OF Kansas COUNTY OF Barber ss.

Alan Vratil

(Employee of Operator) or (Operator)

above-described well, being first duly sworn on oath, says: That I have knowledge of the fact statements, and matters herein contained and the log of the above-described well as filed therewith are true and correct, so help me God.



(Signature) [Signature]

(Address) Medicine Lodge, KS 67104

SUBSCRIBED AND SWORN TO before me this 25 day of August, 19 95

Glenda Morrison
Notary Public

My Commission Expires: 10/14/98