

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
130 S. Market, Room 2078  
Wichita, KS 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-151-22,019 -00-00

LEASE NAME Dauner

WELL NUMBER 1-21

TYPE OR PRINT  
NOTICE: Fill out completely and return  
to Cons. Div. office within 30 days.

330 Ft. from (S)N Line of Section (circle one)

4950 Ft. from (E)W Line of Section (circle one)

LEASE OPERATOR F. G. Holl Company, L.L.C.

SPOT LOCATION - SW - SW - SW

ADDRESS 6427 E. Kellogg P.O. Box 780167

SEC. 21 TWP. 295 S. RGE 12 (E) or (W)

CITY, STATE, ZIP Wichita, Kansas 67278-0167

COUNTY Pratt

PHONE# (316) 684-8481 OPERATORS LICENSE NO. 5056

Date Well Completed \_\_\_\_\_

Character of Well Oil  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Date Plugging Commenced Oct. 16, 1997

Date Plugging Completed Oct. 23, 1997

The plugging proposal was approved on 8/3/97 (date)  
by Steve Durrant (KCC District Agent's Name)

Is ACO-1 filed? Yes If not, is well log attached? \_\_\_\_\_

Producing Formation(s) Marmaton Formation Depth to Top 4288' Bottom 4308' T.D. 4770'

Show depth and thickness of all water, oil and gas formations. PBTD 4737'

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULL OUT
	SURFACE	0	311'	8 5/8"	311'	0
	CASING	0	4769'	4 1/2"	4769'	2700'

Described in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each set.

On Oct. 16, the T.D. was 4185' Fill back with sand and 4 sx cement. On Oct. 17, shot off casing at 2700', pulled and laid down 64 - 4 1/2" joints of casing. On Oct. 23, completed plugging with 300 lbs. hulls, 10' sx. gel, 50 sx. cement, 10 sx. gel, 100 lbs. hulls, 8 5/8 wiper plug, 100 sx. cement, 60/40 poz, 6% gell.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Pratt Well Service INC.

License No. 5893

Address P.O. Box 847 Pratt, Kans. 67124

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: F. G. Holl Company, L.L.C.

STATE OF Kansas COUNTY OF Pratt, ss.

Stephen E. Hart / Office Manager (Employee of Operator or (Operator) of above-described well, being first duly

sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the Log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Stephen E. Hart

(Address) P. O. Box 847 Pratt, Kans. 67124

SUBSCRIBED AND SWORN TO before me this 30th day of October, 1997

Kenneth W. Furgason  
Notary Public

My Commission Expires: 06/19/00

KENNETH W. FURGASON  
Notary Public - State of Kansas  
My Appl. Expires 06/19/00

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 3 1997  
CONSERVATION DIVISION  
Wichita, Kansas  
11-03-97  
Form CP-4  
Revised 12-9.