

15.151-20636-00-00


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202

Pratt County, Sec. 18 Twp. 29S Rge. 12W E. 4W  
Location as "NE/CNW/SW" or footage from lines \_\_\_\_\_

C-NW SW  
Lease Owner Beren Corporation  
Lease Name Killingsworth Well No. 1  
Office Address 970 Fourth Financial Center, Wichita, KS  
Character of Well (Completed as Oil, Gas or Dry Hole) 67202



Locate well correctly on above Section Plot

Dry Hole  
Date Well completed May 16, 1979  
Application for plugging filed Verbal Application 19\_\_  
Application for plugging approved Verbal Approval 19\_\_  
Plugging commenced May 16, 1979  
Plugging completed May 16, 1979  
Reason for abandonment of well or producing formation \_\_\_\_\_

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Wm. T. Owen  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4,726'  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				12-3/4"	239'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled hole with heavy rotary mud from 4,726 ft. (rotary total depth) to 600 ft. Set plug at 600 ft. and cemented with 50 sacks cement. Filled hole with heavy rotary mud from 600 ft. to 228 ft. Set plug at 228 ft. and cemented with 50 sacks cement. Filled hole with heavy rotary mud from 228 ft. to 40 ft. Set solid plug at 40 ft. and cemented to cellar with 20 sacks cement, 4 sacks cement in rat hole.

Plugging operations accomplished utilizing Halliburton Oil Well cementing pump truck through 4 1/2 inch drill pipe.

RECEIVED  
STATE CORPORATION COMMISSION

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Halliburton Services 410 Union Center Bldg., Wichita, KS 67202

STATE OF Kansas COUNTY OF Sedgwick, ss.  
Merle Britting, Agent ~~XXXXXXXXXX~~ of owner ~~XXXXXXXXXXXXXXXXXXXX~~

of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Merle Britting  
200 N. Main, Wichita, Kansas 67202  
(Address)

SUBSCRIBED AND SWORN TO before me this 24th day of May, 19 79



Elsie Willison  
Notary Public.

My commission expires July 25, 1982

KANSAS DRILLERS LOG

COMPANY Beren Corporation

SEC. 18 T. 29S R. 12W

FARM Killingsworth NO. 1

LOC. C-NW SW

COUNTY Pratt

ROTARY TOTAL DEPTH 4,726'

COMM. April 30, 1979

COMP. May 16, 1979

CONTRACTOR H-30, Inc. (Rig #3)

ISSUED May 24, 1979

casing  
12 3/4" Set at 239' cemented w/425 sxs cement  
10 3/4"  
8 5/8"  
5 1/2"  
4 1/2"

ELEVATION 1,906' GR.

FIGURES INDICATE BOTTOM OF FORMATIONS

Sand and Shale	220'
Red Bed	240'
Shale	593'
Shale and Lime	3,157'
Lime and Shale	3,382'
Shale and Lime	3,580'
Lime and Shale	4,090'
Lime	4,094'
Lime and Shale	4,482'
Shale and Lime	4,497'
Lime and Shale	4,604'
Lime	4,711'
Lime and Shale	4,726'
Rotary Total Depth	4,726'

I hereby certify the above and foregoing to be a true and correct log of the above described well as shown by the drilling reports.

H-30, INC.

*Merle Britting*  
Merle Britting

State of Kansas }  
County of Sedgwick } SS:

Subscribed and Sworn to before me a Notary Public in and for said county and state this 24th day of May, 1979.

*Elsie Willison*  
Elsie Willison - Notary Public

My Commission Expires:  
July 25, 1982

RECEIVED  
STATE CORPORATION COMMISSION

MAY 25 1979

STATE CORPORATION COMMISSION  
Wichita, Kansas