

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Dorby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-151-21495-00-00

LEASE NAME HIRT

WELL NUMBER 2-29

SPOT LOCATION SE NW

SEC. 29 TWP. 29 RGE. 12 (W) or (E)

COUNTY Pratt

Date Well Completed _____

Plugging Commenced 5-27-88

Plugging Completed 6-13-88

LEASE OPERATOR F.G. HOLL COMPANY

ADDRESS P.O. Box 158 Belpre, Kansas 67519

PHONE (316) 995-3171 OPERATORS LICENSE NO. 5056

Character of Well Gas
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Dodge City, Kansas

Is ACO-1 filed? yes If not, is well log attached? _____

Producing formation _____ Depth to top _____ bottom T.O. 4689'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				<u>3/4</u>	<u>109 jts</u>	<u>109 rods</u>
				<u>2 3/8</u>	<u>87 jts</u>	<u>87 jts.</u>
				<u>4 1/2</u>		<u>55 jts.</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.


6-13-88 Top hole plugging: Set plug at 2400'. Shot 2214--55 jts. recovered. 4 hulls, 10 gel, 50 sx. 10 gel, 1 hull, plug, 100 sx. 60-40 pz and 6% gel. 600 max. pressure, 300# shut in pressure, 4' down to cement.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor PRATT WELL SERVICE, INC. License No. 5893
Address Box 847 Pratt, Kansas 67124

STATE OF Kansas COUNTY OF Pratt, ss.

RECEIVED
Judy Berry, plugging contractor employee of Pratt Well Service, Inc. or State Corporation Commission of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.



06-24-88 (Signature) Judy Berry
CONSERVATION DIVISION
Wichita, Kansas (Address) Box 847 Pratt, Ks.

SUBSCRIBED AND SWORN TO before me this 22 day of June, 1988

My Commission expires: Feb. 6, 1989

Dorothy M. Ferguson
Notary Public

STERLING DRILLING CO.

BOX 129

STERLING, KANSAS 67579

WELL LOG - - - - - HIRT #2-29
Located: C SE NW, Section 29-29S-12W, Pratt County, Kansas

OWNER: F. G. Holl

ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: October 23, 1984

COMPLETED: October 31, 1984

TOTAL DEPTH: 4689'

LOG

CASING RECORD

0 - 215 Clay and Sand

Ran 6 joints new 8 5/8", 23# casing.
242.76' pipe set at 256' K.B. Cemented
with 200 sacks Class A, 2% gel and 3% cc.
Plug down at 12:00 noon, 10-23-84, by
Howco.

215 - 257 Red Bed

257 - 350 Shale and Red Bed

350 - 4689 Lime and Shale

Ran 76 joints new 4 1/2", 10.5# casing.
3023.28' pipe set at 3031' K.B. Cemented.
with 175 sacks 50/50 Pozmix with our
regular additives. Plug down at 9:30 PM,
10-31-84, by Howco.

Deviation Surveys: 2° at 2043'
3/4° at 4515'
3/4° at 4689'

RECEIVED
STATE CORPORATION COMMISSION

MAY 24 1988

CONSERVATION DIVISION
Wichita, Kansas