

STATE OF KANSAS  
 STATE CORPORATION COMMISSION  
 200 Colorado Derby Building  
 Wichita, Kansas 67202

WELL PLUGGING RECORD  
 K.A.R.-82-3-117

API NUMBER 15-151-21,976 -00.00

LEASE NAME HIRT A

WELL NUMBER 1-29

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

         Ft. from S Section Line

         Ft. from E Section Line

C E 1/2 NE NW  
 SEC. 29 TWP. 29 RGE. 12 (E or W)

LEASE OPERATOR F. G. HOLL COMPANY

ADDRESS 6427 EAST KELLOGG P O BOX 780167 WICHITA, KS. 67278 COUNTY PRATT

PHONE#(316) 684-8481 OPERATORS LICENSE NO. 5056 Date Well Completed         

Character of Well Oil Plugging Commenced 3-28-91

(Oil, Gas, D&A, SWD, Input, Water Supply Well) Plugging Completed 4-2-91

The plugging proposal was approved on April 2, 1991 (date)

by Steve Durant (KCC District Agent's Name).

Is ACO-1 filed? YES If not, is well log attached?         

Producing Formation MISSISSIPPIAN Depth to Top          Bottom          T.D. 4770

PERFS: 4376-4388 TOP OF CEMENT: 3580 BOND LOG         

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

RECEIVED  
 STATE CORPORATION COMMISSION

Formation	Content	From	To	Size	Put In	Pulled out
				3/4 RODS		172
				2 3/8 TBC.		140 JTS
				8 5/8		0
		0	4759	4 1/2	4759	2200' 52 JTS.

MAY 02 1991

JTS CONS. DIVISION  
 Wichita, Kansas

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from          feet to          feet each set.

3-29-91: PULLED AND LAYED DOWN RODS & TUBING, DUMPED 8 BBLs. OF SAND IN THE WELL.

4-1-91: TOP OF SAND AT 4200'. DIA LOG SHOT 4 1/2 AT 2200'. ALSO DUMPED 2 SX. OF CEMENT BEFORE CASING WAS SHOT OFF.

4-2-91: PULLED 52 JTS. PLUS CUTOFF JOINT, RIGGED DOWN & MOVED OFF. (SEE BACK OF PAGE)

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor PRATT WELL SERVICE, INC. License No. 5893

Address P O BOX 847 PRATT, KANSAS 67124

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: F G HOLL COMPANY

STATE OF KANSAS COUNTY OF PRATT, ss.

JUDY BERRY

PLUGGING CONTRACTOR

(Employee of ~~XXXXXXXXXXXXXXXXXXXX~~)  
 above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Judy Berry

(Address) PWS, Inc. Pratt, Ks.



SUBSCRIBED AND SWORN TO before me this 30th day of April, 1991

Dorothy M. Ferguson  
 Notary Public

My Commission Expires Feb. 6, 1993

HALLIBURTON TOP HOLE PLUGGED THE WELL WITH 300# HULLS, 10 SX GEL, 50 SX CEMENT,  
10 SX. GEL, 100# HULLS, 100 SX. CEMENT. 60-40 POZ, 6%. MAX PRESSURE 500#,  
ISIP 250#.

4/2/71  
HALLIBURTON  
TOP HOLE PLUGGED THE WELL WITH 300# HULLS, 10 SX GEL, 50 SX CEMENT,  
10 SX. GEL, 100# HULLS, 100 SX. CEMENT. 60-40 POZ, 6%. MAX PRESSURE 500#,  
ISIP 250#.

# STERLING DRILLING COMPANY

BOX 129

STERLING, KANSAS 67579

WELL LOG ----- HIRT "A" 1-29

Located: C E/2 NE NW, Section 29-29S-12W, Pratt County,  
Kansas

OWNER: F. G. Holl Company

ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: January 15, 1990

COMPLETED: January 24, 1990

TOTAL DEPTH: 4765'

## LOG

## CASING RECORD

0 - 200 Sand and Clay  
200 - 333 Red Bed  
333 - 4765 Shale and Lime

Ran 9 joints 8 5/8", 23# new and used casing. 318.46' pipe set at 332' K.B. Cemented with 250 sacks 60/40 Pozmix with 2% gel and 3% cc. Plug down at 1:30 P.M. 1-15-90, by Howco. Good returns to surface.  
Ran 115 joints 4 1/2", 10.5# new and used casing. 4747.16' pipe set at 4759' K.B. Cemented with 100 sacks Lite, followed with 125 sacks F. G. Holl mix. Plug down at 11:15 PM, 1-24-90, by Halliburton. Centralizers on Joints 1, 7 and 13. Shoe joint 20.15 (365.19' of used casing.)

Deviation Surveys: 1/2° at 2830'  
3/4° at 4340'  
1 1/4° at 4765'

RECEIVED  
STATE CONSERVATION DIVISION

MAR 26 1991

CONSERVATION DIVISION  
Wichita, Kansas