

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

15-097-20166-0001

API NUMBER

LEASE NAME Ralstin

WELL NUMBER B-1

SPOT LOCATION C SW SE

SEC. 36 TWP. 29 RGE. 20 (E) or (W)

COUNTY Kiowa

Date Well Completed

Plugging Commenced 4-21-86

Plugging Completed 5-2-86

TYPE OR PRINT

NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR J. Mark Richardson

ADDRESS 640 Century Plaza Bldg. Wichita, Ks. 67202

PHONE # (316) 262-3192 OPERATORS LICENSE NO. 5414

Character of Well Oil  
(Oil, Gas, D&A, SWD, Input, Water Supply, Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dodge City, Kansas

Is ACO-1 filed?                      If, not, is well log attached?                     

Producing formation                      Depth to top                      bottom                      T.D. 5274'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	1127'	none
				4-1/2"	5273'	3563'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from    feet to    feet each set.

Plugged off bottom with sand to 4740' and 4 sacks cement. Shot pipe @ 4237', 4020', 3859', 3733', 3563', pulled a total of 87 joints (3563') of 4-1/2" casing. Plugged surface with 3 hulls, 15 gel, 50 sks. 60/40 pos, 10 gel, 1 hull, 100 sks. 60/40 pos. Plugging Complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling License No. 6050  
Address P.O. Box 347 Chase, Kansas 67524

5-8-86

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (employee of operator) or  
(operator) of above-described well, being first duly sworn on oath, says: That  
I have knowledge of the facts, statements, and matters herein contained and  
the log of the above-described well as filed that the same are true and  
correct, so help me God.

(Signature) R. Darrell Kelso

(Address) Box 347 Chase, Ks. 67524

SUBSCRIBED AND SWORN TO before me this 7th day of May, 19 86

My Commission expires:



Irene Hoover  
Notary Public

GABBERT-JONES, INC.  
WICHITA, KANSAS  
DRILLERS' WELL LOG

RALSTIN "B" #1 OWWO  
C-SW-SE Sec. 36-29S-20W  
Kiowa County, Kansas

Old Information: Commenced: 5-21-73  
Operator: Imperial Oil Co. Completed: 6-8-73  
TD 5274


New Information: Commenced: 1-14-84  
Operator: J. Mark Richardson Completed: 1-16-84  
TD 5270

Depth		Formation	Remarks
From	To		
0	1748	Cement-Heavy Mud	1127' of 8 5/8" csg. with
1748	5270	Heavy Mud-Cement	500 sks Cement (was Imperial
			Oil Co. #1 National Research
			Foundation)
	5270-TD		


Ran 130 jts. of 10 1/2#  
4 1/2" csg. set @ 5269' cemen-  
ted w/220 sks RFC  
PD @ 2:00 P.M. 1-16-84

State of Kansas )  
County of Sedgwick ) I, the undersigned, being duly sworn on oath,  
state that the above Drillers' Well Log is  
true and correct to the best of my knowledge  
and belief and according to the records of this  
office.


GABBERT-JONES, INC.

  
James S. Sutton, II -- President

Subscribed & Sworn to before me  
this twenty-sixth day of January, 1984.

  
Lola Lenore Costa

My Commission expires November 21, 1984.



RECEIVED  
STATE CORPORATION COMMISSION

APR 9 1986

CONSERVATION DIVISION  
Wichita, Kansas