


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

FORD County. Sec. 26 Twp. 29S Rge. (E)22 (W)
Location as "NE/CNWxSWx" or footage from lines APPROX. C NE SW
Lease Owner DAY PETROLEUM CORP.
Lease Name DARST Well No. 1
Office Address 1450 S. HARLAN, DENVER, COLO. 80226
Character of Well (completed as Oil, Gas or Dry Hole) DRY HOLE
Date well completed Nov. 28, 19 66
Application for plugging filed (PHONE 11/28/66) Nov. 30, 19 66
Application for plugging approved Nov. 28, 19 66
Plugging commenced Nov. 28, 19 66
Plugging completed Nov. 28, 19 66
Reason for abandonment of well or producing formation _____



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well MR. EVES
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 5362 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	464	8-5/8	464	NONE

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

FILLED HOLE WITH HEAVY MUD TO 510 FEET. SET FIRST PLUG @ 510 FEET WITH 35 SACKS CEMENT.
FILLED HOLE WITH HEAVY MUD TO 45 FEET. SET SECOND PLUG @ 45 FEET WITH 15 SACKS CEMENT.
JOB BY GLOBE CEMENTING Co., COMPLETE @ 10:30 AM, Nov. 28, 1966.

RECEIVED
STATE CORPORATION COMMISSION

DEC 2 1966

CONSERVATION DIVISION
Wichita, Kansas

12-2-66

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor GABBERT-JONES, INC.
Address 830 SUTTON PLACE, WICHITA, KANSAS

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
E. F. HALL (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) E. F. Hall

830 SUTTON PLACE, WICHITA, KANSAS 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 30TH day of NOVEMBER, 19 66

My commission expires FEBRUARY 1, 1968

Barbara J. Layton
BARBARA J. LAYTON Notary Public.

GABBERT-JONES, INC.
 WICHITA, KANSAS
 DRILLERS' WELL LOG

RECEIVED
 CONSERVATION DIVISION
 WICHITA, KANSAS

DEC 2 1966

DARST #1
 APPROX. C NE SW SECTION 26-29S-22W
 FORD COUNTY, KANSAS

COMMENCED: NOVEMBER 5, 1966
 COMPLETED: NOVEMBER 28, 1966

OPERATOR - DAY PETROLEUM CORPORATION

DEPTH		FORMATION	REMARKS
FROM	TO		
0	150	CLAY AND SAND	
150	464	RED BED	RAN 18 JOINTS OF 8-5/8" CASING, SET @ 464' w/275 SACKS CEMENT.
464	1384	RED BED	
1384	1407	ANHYDRITE	
1407	1420	RED BED	
1420	1815	RED BED AND SHALE	
1815	2660	SHALE AND LIME	
2660	2710	LIME	
2710	4600	LIME AND SHALE	
4600	4800	LIME	
4800	4875	LIME AND SHALE	
4875	5080	LIME	
5080	5145	LIME AND SHALE	
5145	5170	SHALE AND SAND	
5170	5226	LIME	
5226	5235	CONGLOMERATE	
5235	5295	LIME	
5295	5362	LIME AND SHALE	
5362	TD		DRY AND ABANDONED.

I, E. E. HALL, CERTIFY THIS IS A CORRECT COPY OF THE DRILLERS' LOG FOR THE WELL DRILLED IN THE APPROXIMATE C NE SW SECTION 26-29S-22W, FORD COUNTY, KANSAS, TO THE BEST OF MY KNOWLEDGE AND BELIEF.

E. E. Hall
 E. E. HALL

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

BEFORE ME, THE UNDERSIGNED, A NOTARY PUBLIC WITHIN AND FOR SAID COUNTY AND STATE, ON THIS 30TH DAY OF NOVEMBER, 1966, PERSONALLY APPEARED E. E. HALL, TO ME PERSONALLY KNOWN TO BE THE IDENTICAL PERSON WHO EXECUTED THE WITHIN AND FOREGOING INSTRUMENT, AND ACKNOWLEDGED TO ME THAT HE EXECUTED THE SAME AS HIS FREE AND VOLUNTARY ACT AND DEED FOR THE USES AND PURPOSES THEREIN SET FORTH.

IN WITNESS WHEREOF, I HAVE HEREUNTO SET MY HAND AND OFFICIAL SEAL THE DAY AND YEAR LAST ABOVE WRITTEN.

Barbara J. Layton
 BARBARA J. LAYTON, NOTARY PUBLIC

MY COMMISSION EXPIRES FEBRUARY 1, 1968.