


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation CommissionP. O. Box 17027
Wichita, Kansas 67217
NORTHLocate well correctly on above.
Section Plat

WELL PLUGGING RECORD

Kiowa County. Sec. 36 Twp. 29S Rge. (E) 20 (W)
Location as "NE/CNW/SW" or footage from lines. Ap C SE NW
Lease Owner Imperial Oil Co.
Lease Name Dean Well No. 1
Office Address 780 Fourth Nat'l Bk Bldg., Wichita, Ks.
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed October 7, 1973
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced October 7, 1973
Plugging completed October 7, 1973
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes (Russell Biberstein of Attica)

Name of Conservation Agent who supervised plugging of this well
Producing formation Depth to top Bottom Total Depth of Well 5291 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	Surface	0	562'	8-5/8"	562'	None
	Casing					

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Mud from Total Depth to 400 Feet,
40 sax Cement Plug; Mud to 40 Feet,
1/2 sax Halls, Plug Bridged & 15 sax
Cement to Base of Cellar; 3 sax
Cement in Rat Hole. Job Completed
@ 5:00 A.M.

RECEIVED
STATE CORPORATION COMMISSION

OCT 10 1973

CONSERVATION DIVISION
Wichita, Kansas

10-10-73

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Sun Oil Well Cementing, Inc.
Address Box 169, Great Bend, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

Clarence Michael of Sage Drilling Co. (employee or owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Clarence Michael
500 Bitting Bldg., Wichita, Kansas
(Address)

Subscribed and Sworn to before me this 9th day of October, 1973.

My commission expires November 26, 1974

Louise K. Whitted, Notary Public.

DRILLERS LOG

DEAN NO. 1

CASING RECORD:	OPERATOR: Imperial Oil Co.	DESCRIPTION:
8-5/8" @ 562'	CONTRACTOR: Sage Drilling Co.	Ap C SE NW
w/450 sax cement	COMMENCED: September 20, 1973	Sec. 36-29S-20W
TOTAL DEPTH:	COMPLETED: October 7, 1973	Kiowa County, Kansas
5291'		ELEVATION: 2349KB


<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Surface Soil & Sand	0	160	
Sand	160	195	
Clay & Sand	195	260	
Shale	260	546	
Anhydrite	546	564	
Shale	564	1130	
Shale & Lime	1130	1625	
Lime	1625	2010	
Lime & Shale	2010	2525	
Lime	2525	3395	
Lime & Shale	3395	4125	
Lime	4125	4275	
Lime & Shale	4275	4475	
Lime	4475	5291	D&A

RECEIVED
STATE CORPORATION COMMISSION
OCT 10 1973
CONSERVATION DIVISION
Wichita, Kansas

I certify that this is a true and correct copy of the above log to the best of my knowledge.

SAGE DRILLING CO., INC.

By Clarence Michael
Clarence Michael



Subscribed and sworn to before me this 9th day of October, 1973.

Louise K. Whitted
Louise K. Whitted, Notary Public

My commission expires:
November 26, 1974.