


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

Pratt County, Sec. 9 Twp. 28 Rge. 14 (E) W (W)

Location as "NE/CNW/SWK" or footage from lines G NE SW
Lease Owner Crescent Oil and Gas Corporation
Lease Name Heimuller Well No. 1
Office Address P.O. Box 2460, Dallas, Texas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 6/22/63 as a dry hole 19 63
Application for plugging filed June 22 19 63
Application for plugging approved June 22, Verbally 19 63
Plugging commenced June 22 19 63
Plugging completed June 22 19 63
Reason for abandonment of well or producing formation _____



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production _____ 19 _____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Archie V. Elving
Producing formation Dry-None Depth to top _____ Bottom _____ Total Depth of Well 4760 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
					10 3/4"	354

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Pumped in heavy mud from total depth to 325'. Set plug in 10 3/4" surface at 325'. Ran 37 sacks of cement on top of plug through drill pipe. Put mud and hulls on top of cement to 35'. Ran second plug and cemented to the surface.

Plugged and Abandoned

RECEIVED
STATE CORPORATION COMMISSION
JUL 1 1963
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Tomlinson-Kathol, Inc.
Address Town Plaza, Wichita, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Charles Stacey
P.O. Box 485, Ellinwood, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 28th day of June, 1963

Frederic M. Stevenson, Notary Public
My commission expires 8-20-63

Frederic M. Stevenson
Notary Public.

DRILLERS LOG
 CRESCENT OIL & GAS CORP.
 I. HEIMULLER
 C NE SW, SEC. 9-28-14W
 PRATT COUNTY, KANSAS

Contractor - Tomlinson-Kathol, Inc.

Commenced: 6/5/63
 Completed: 6/21/63
 Elevation: 2033 KB


<u>From</u>	<u>To</u>	<u>Description</u>	<u>Remarks</u>
0	67	Clay	
67	190	Sand - Gravel	
190	335	Clay - Shale	335' 10-3/4" surf. csg. w/275 sacks cement
335	360	Shale	
360	800	Shale, Sand	
800	1006	Shale & Red Bed	
1006	2010	Shale	
2010	2200	Shale - Lime streaks	
2200	2565	Lime - Shale	
2565	2780	Lime & Shale	
2780	2920	Shale - Lime - Sand	
2920	3525	Lime & Shale	
3525	3646	Shale & Lime	
3646	3841	Lime - Shale	
3841	3985	Shale - Lime	Heebner 3817
3985	4475	Lime	Brown Lime 3981
4475	4527	Lime - Chert - Shale	Lansing 4004
4527	4585	Mississippian	Base K.C. 4357
4585	4615	Chert	Miss. 4471
4615	4671	Lime - Shale - Chert	Kinderhook 4499
4671	4700	Chert - Shale	Viola 4550
4700	4760	Chert & Shale	Simpson Sh 4633
4760		Total Depth	Simpson Sd 4654 Arbuckle 4733

I certify to the best of my knowledge and belief, the above represents a true and accurate driller's log record of the captioned well.


 Richard C. Davis

STATE OF KANSAS
 COUNTY OF SEDGWICK SS

Subscribed and sworn to before me this 25th day of June 1963.


 Esther Lamone, Notary Public

My Commission Expires: 1/19/65

RECEIVED
 STATE CORPORATION COMMISSION

JUL 1 1963

COMMERCIAL DIVISION
 WICHITA, KANSAS