

STATE OF KANSAS
 STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
 Make Required Affidavit
 Mail or Deliver Report to:
 Conservation Division
 State Corporation Commission
 800 Bitting Building
 Wichita, Kansas

Pratt County. Sec. 8 Twp. 28 Rge. 14 (E) W (W)

Location as "NE/CNW 1/4 SW 1/4" or footage from lines Ctr. NE NE SE

Lease Owner Lion Oil Company

Lease Name Maercker Well No. 1

Office Address Box 552, Pratt, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 8-31-1950

Application for plugging filed 8-31-50

Application for plugging approved 8-31-1950

Plugging commenced 8-31-1950


Plugging completed 8-31-1950

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging, was commenced? Yes

NORTH



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well C. D. Stough

Producing formation Depth to top Bottom Total Depth of Well 4790 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8"	378'	773'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other-plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Heavy mud to 250' set bridging plug with 15 sacks of cement
 Heavy mud to 30' set bridging plug with 10 sacks of cement

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Vernon Hayes
 Address Box 552
 Pratt, Kansas

STATE OF Kansas COUNTY OF Pratt ss.
 Vernon Hayes (employee of owner) or (owner or operator) of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *Vernon Hayes*
 Box 552, Pratt, Kansas
 (Address)

SUBSCRIBED AND SWORN to before me this 9th day of September, 1950.

My commission expires with office
Patricia Hammigal Reg. of Deeds
 Notary Public. *rw*

PLUGGING
 FILE SEC. *L.T. 24 R 14*
 BOOK PAGE 25 LINE 11

SEP 11 1950
 09-11-50

Maercker Well No. 1

NE NE SE
Sec. 8-28S-14W
Pratt County
Kansas

Contractor: The R. W. Rine Drilling Company
Started 8/12/50 Finished 8/31/50

LOG

Sand - Gravel - Clay	0	=	510	
Red Bed - Red Rock	510	=	780	8-5/8" @ 778' w/ 400 Sx.
Cement	720	=	780	
Shale - Shells	780	=	1420	Syfo @ 1000' - 3/4°
Salt	1420	=	1504	Syfo @ 1500' - 1/2°
Salt - Shale	1504	=	1760	
Shale - Shells	1760	=	1925	
Sandy Lime - Shale	1925	=	2035	Syfo @ 2000' - 1/2°
Sandy Lime	2035	=	2245	
Lime - Shale	2245	=	2340	
Sandy Lime - Shale	2340	=	2595	Syfo @ 2500' - 1/2°
Shale - Lime	2595	=	3404	
Lime	3404	=	3461	
Lime - Shale	3461	=	3575	Syfo @ 3500' - 3/4°
Lime	3575	=	3626	
Lime - Shale	3626	=	3725	
Lime	3725	=	3770	
Lime - Sand	3770	=	3928	
Lime	3928	=	4410	
Lime - Shale	4410	=	4445	
Lime	4445	=	4473	
Lime - Shale	4473	=	4515	
Cherty Lime	4515	=	4555	
Lime - Shale	4555	=	4590	
Lime	4590	=	4628	
Lime - Shale	4628	=	4637	
Simpson Sand	4637	=	4658	
Lime - Shale	4658	=	4740	
Lime	4740	=	4790	

Tops: Heebner	3817
Douglas	3883
Brown Lime	3971
Lansing	3990
Mississippi	4450
Kinderhook	4471
Viola	4546
Simpson Shale	4619
Simpson Sand	4632
Arbuckle	4731
T.D.	4788

State of Kansas)
County of Sedgwick) ss.

I, Clyde W. Goddard, do hereby certify that the above is a true and accurate log of the Maercker Well No. 1, located in the NE NE SE of Section 8-28S-14W, Pratt County, Kansas.

Clyde W. Goddard

Subscribed to and sworn before me this 5th day of September, 1950.

My commission expires Dec. 29, 1952

B. M. Green
Notary Public

PRATT

SEP 11 1950

PLUGGING
FILE SEC. 8-28S-14W
COOK PAGE 25-LINE 11