


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Recor...
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Pratt County, *Sec 24 Twp 28S Rge 14 XX (W)

Location as "NE/CNW¹/₄SW¹/₄" or footage from lines SE SE SE
Lease Owner Lohmann-Johnson Drilling Co., Inc.
Lease Name Thompson Well No. 1
Office Address 320 Indiana Bank Bldg., Evansville, Indiana
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed November 21 19 53
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced November 21, 1953 19
Plugging completed November 21, 1953 19
Reason for abandonment of well or producing formation Dry Hole
If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well
Producing formation Depth to top Bottom Total Depth of Well 4670 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Heavy Mud - Total Depth to 300
Bridge formed - 20 sacks cement dumped
300 to 40' - Mud
Bridge formed - 10 sacks cement dumped

RECEIVED
12-10-53

Name of Plugging Contractor Halliburton Oil Well Cementing Co., Inc.
Address

STATE OF Indiana, COUNTY OF Vanderburgh, ss.
J. B. Lohmann (employee of owner or (owner or operator) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
(Address)

SUBSCRIBED AND SWORN to before me this 8th day of December, 19 53

[Signature]

My commission expires November 5, 1957

Notary Public.

PLUGGING
FILE SEC 24 T 28 R 14W
BOOK PAGE 144 LINE 33

T H O M P S O N N O. 1

WELL RECORD

Location: Section 29-28S-19W, Pratt County, Kansas

Operator: Lohmann-Johnson Drilling Co., Inc., Etal
 320 Indiana Bank Building
 Evansville, Indiana

Contractor: Lohmann-Johnson Drilling Co., Inc.
 320 Indiana Bank Building
 Evansville, Indiana

Casing Record: Set 11 Jys. (345.76') 8-5/8" 24# Casing @ 343' W/165 sks

Commenced: November 4, 1953

Completed: November 21, 1953

LOG

<u>FROM</u>	<u>TO</u>	<u>FORMATION</u>
0	163	Sand
163	350	Sand & Red bed
350	810	Red bed & Shells
810	825	Anhydrite
825	1600	Shale & Shells
1600	2036	Lime & Shale
2036	2150	Shale & Lime
2150	2225	Lime
2225	2355	Lime & Shale
2355	2605	Shale & Lime
2605	2735	Lime & Shale
2735	3097	Shale & Lime
3097	3395	Lime & Shale
3395	3516	Shale & Lime
3516	3681	Lime & Shale
3681	3757	Shale & Lime
3757	3760	Shale
3760	3880	Sand & Shale
3880	3958	Shale & Lime
3958	4033	Lime
4033	4040	Lime, Broken
4040	4130	Lime & Chert
4130	4324	Lime
4324q	4370	Lime & Chert
4370	4382	Lime
4382	4403	Chert - Miss.
4403	4420	Lime
4420	4448	Shale & Lime
4448	4456	Lime - Viola
4456	4465	Lime
4465	4495	Shale & Lime
4495	4520	Lime & Shale
4520	4556	Lime, Shale & Sand
4556	4583	Sand, Shale & Chert
4583	4636	Lime & Shale
4636	4670	Lime
4670		TOTAL DEPTH

Dry and Abandoned

PLUGGING
 FILE SEC 24 T 28 R 14W
 BOOK PAGE 144 LINE 33

The undersigned, Lohmann-Johnson Drilling Co., Inc., hereby certifies that the above Log is a true and correct log of the formations encountered in drilling the above Well as reflected by the Daily Drilling Reports.

LOHMANN-JOHNSON DRILLING CO., INC.

Wallace Sugrator

Subscribed and sworn to before me
this 24th day of November, 1953

Robert Zuelke

Notary Public

My Commission expires November 5, 1957