

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Pratt

County. Sec. 23 Twp. 28 Rge. (E) 14 (W)

Location as "NE/CNW/SW" or footage from lines. NE NE NE/4

Lease Owner Armer, Inc.

Lease Name Biddinger Well No. 1

Office Address 710 Petroleum Building, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed Dec. 11, 1956

Application for plugging filed " " 19 "

Application for plugging approved " " 19 "

Plugging commenced " " 19 "

Plugging completed " " 19 "

Reason for abandonment of well or producing formation dry.

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? M. A. Rives

Name of Conservation Agent who supervised plugging of this well

Producing formation Depth to top Bottom Total Depth of Well 4625 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	310'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Mudded hole to 300 ft., set plug and  
ran 20 sacks cement and 1/2 sack hulls through  
drill pipe. Mudded hole to 40 ft., set plug - 1/2  
sack hulls and 10 sacks cement for cap.

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 15 1956  
15-15-56  
CONSERVATION DIVISION

Name of Plugging Contractor Armer, Inc.  
Address Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
L. C. Sponenberg (employee of owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *L. C. Sponenberg*  
(Address)

SUBSCRIBED AND SWORN TO before me this 13th day of December, 1956

*Rose Turley*  
Notary Public.

My commission expires February 13, 1960.

PLUGGING  
FILE SEC. 23 T. 28 R. 14 W  
BOOK PAGE 125 LINE 15

KANSAS GEOLOGICAL SOCIETY  
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU  
KANSAS GEOLOGICAL SOCIETY BUILDING  
508 EAST MURDOCK - WICHITA, KANSAS

COMPANY **Armor, Inc.**

SEC. **23** T. **28** R. **14S**  
LOC. **HS 03 52**

FARM **Blodinger**

NO. **1**

TOTAL DEPTH **4625**


COUNTY **Frost**

COMM. **11/21/56**

COMP. **12/11/56**

KANSAS

SHOT OR TREATED



CONTRACTOR **Armor, Inc.**

ISSUED

CASING

20	10	
15	8	<b>310'</b>
12	6	
13	5	

ELEVATION **1934 S.D.**

PRODUCTION **D & A**

FIGURES INDICATE BOTTOM OF FORMATIONS

Sand	135
Sand, Red Bed & Shale	770
Anhydrite	802
Shale, Shells & Red Bed	845
Shale, Shells, Red Bed & Salt	1365
Shale & Shells	1920
Line	1955
Shale & Line	2060
Line	2250
Shale & Line	2410
Shale & Shells	2640
Shale & Line	2800
Shale & Shells	3059
Shale & Line	3195
Line	3550
Line & Shale	3615
Broken Line	3695
Shale & Line	3867
Line	4200
Line & Shale	4335
Cherty Line & Shale	4359
Cherty Line	4390
Chert & Line	4430
Line, Shale & Chert	4465
Shale	4490
Shale & Sand	4520
Shale	4600
Line & Shale	4625

FORMATION TOPS

HEMLOCK	3698	VIOLA	4399
TORONTO	3720	SIMPSON SHALE	4475
BROWN LINE	3863	SIMPSON SAND	4509
LANSING	3879	ARBUCKLE	4591
BASE KANSAS CITY	4224		
WARMATH	4232		
MISSISSIPPI	4331		

I hereby certify that this is a true and correct log of the above described well as shown by the drilling reports.

**ARMOR, INC. RECEIVED**  
STATE CORPORATION COMMISSION

PLUGGING

STATE OF KANSAS    FILE SEC. 23 T. 28 R. 14W  
COUNTY OF WICHITA    BOOK PAGE 125 LINE 15

By Rose Furley DEC 15 1956  
CONSERVATION DIVISION  
Wichita, Kansas

Subscribed and sworn to before me, a notary public, in and for said County and State this 12th day of December, 1956.

My Commission expires February 13, 1960.

Rose Furley  
Notary Public