


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Pratt County. Sec. 22 Twp. 28S Rge. 14W E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines
NW NW

Lease Owner Texas Energies, Inc.
Lease Name HESS Well No. 1
Office Address 306 Bank of Southwest Bldg. Amarillo, T
Character of Well (Completed as Oil, Gas or Dry Hole)
Dry Hole



Locate well correctly on above
Section Plat

Date Well completed 6-4-77 1977
Application for plugging filed 6-4 1977
Application for plugging approved 6-4 1977
Plugging commenced 6-4 1977
Plugging completed 6-4 1977
Reason for abandonment of well or producing formation

Dry Hole
If a producing well is abandoned, date of last production
19

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? yew

Name of Conservation Agent who supervised plugging of this well Dwane Rankin
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4640
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS COMMISSION

CASING RECORD

FORMATIONIE COMPLETE	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	414'	

RECEIVED
NOV 14 1977
CONSERVATION DIVISION
Wichita, Kansas

Describe in detail the manner in which the well was plugged, indicating where the mud fluid
was placed and the method or methods used in introducing it into the hold. If cement or other
plugs were used, state the character of same and depth placed, from _____ feet to
_____ feet for each plug set.

1st plug @420 with 40 sacks.
2nd plug @40 with 15 sacks. 5 sacks in rathole

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor GABBERT-JONES, INC.

STATE OF KANSAS COUNTY OF PRATT, ss.
Edd Geoffroy (employee of owner) or (owner or operator)

of the above-described well, being first duly sworn on oath, says: That I have knowledge of
the facts, statements, and matters herein contained and the log of the above-described well
as filed and that the same are true and correct. So help me God.

(Signature)

Box 176 Pratt, Kansas 67124
(Address)

SUBSCRIBED AND SWORN TO before me this 9th day of November, 1977

My commission expires Sept. 13, 1980

Mary L. Francis
Notary Public.



GABBERT-JONES, INC.
 WICHITA, KANSAS
 DRILLERS' WELL LOG

Lawrence
Edd

Texas Energies #1 Hess
 NW-NW Sec 22-28S-14W
 Pratt County Kansas

Commenced: 5-25-77

Completed: 6-4-77

OPERATOR: TEXAS ENERGIES, INC.

Depth		Formation	Remarks
From	To		
0	195	Soil-Sand-Redbed	Ran 11 jts of 28# 8 5/8" csg set @ 414' Cemented w/300 sks Common 3% CC - 2% Gel PD @ 1:45 a.m. 5-26-77 1" to 60' Cemented w/150 sks Common 3% CC JC @ 5:30 a.m. 5-26-77
195	828	Redbed	
828	838	Anhy	
838	2080	Shale-Shells	
2080	2265	Shale-Lime	
2265	3960	Lime-Shale	
3960	4640	Lime	
	4640 - TD		

RECEIVED
 STATE CORPORATION COMMISSION

NOV 14 1977

CONSERVATION DIVISION
 Wichita, Kansas

DRY & ABANDONED

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

I, the undersigned, being duly sworn on oath, state that the above Drillers' Well Log is true and correct to the best of my knowledge and belief and according to the records of this office.

GABBERT-JONES, INC.

James S. Sutton II
 JAMES S. SUTTON II

Subscribed and sworn to before me this 7th day of June, 1977.

Elizabeth J. Edwards
 ELIZABETH J. EDWARDS-NOTARY PUBLIC

My Commission expires February 6, 1979.

