

KANSAS

RECEIVED
STATE CORPORATION COMMISSION
Rev. 6-4-68

STATE CORPORATION COMMISSION

OCT 20 1977

CONSERVATION DIVISION AGENT'S REPORT

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - - - (of this well)

Operator's Full Name Continental Oil Co.

Complete Address 3535-NW-58th St., Okla. City, Okla. 73112

Lease Name Ed. Brehm Well No. 2

Location N²E-NW-NW Sec. 26 Twp. 28 Rge. 13 (E) (W) X

County Pratt Total Depth 4500

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Rockhold Engineering Inc.

Address Box 698, St. Bend, Ks. 67530 License No. 670

Operation Completed: Hour 10 Am Day 18 Month Oct. Year 1977

The above well was plugged as follows:

911'-10 3/4" casing w/350 s/c Cement - 5 1/2" casing set @ 4499'
Cemented w/380 s/c Cement - prof. @ 3650'-3242'-3128'-3054'
2668'-2508' squeezed w/total of 500 s/c Cement - Plug back
to 3585' - push plug to 2500' - sand back to 2475' mix
& dump 5 s/c Cement on top. Set 20' Rock bridge
@ 350' - Dump 7 yards ready mix Cement to top of
Casing. Recovered 2250' 5 1/2" Casing
Pratt Transit Mix - Pratt, Kans - 67124

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 10-20-77

Signed: [Signature]
Well Plugging Supervisor

INV. NO. 6060-4