

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

FEB 24 1964

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Pickrell Drilling Co. 15-095 ~~1537~~-0000

Complete Address: 705 4th National Bldg., Wichita, Kansas

Lease Name Bock Well No. # 2

Location C W/2 SW SW Sec. 7 Twp. 28 Rge. 7 (E) (W) W

County Kingman Total Depth 4085

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: _____

Plugging Contractor: Pickrell Drilling Co.

Address: 705 4th National Bldg., Wichita, Kansas License No. _____

Operation Completed: Hour 11:15 PM Day 21st Month Feb. Year 1964

The Above well was plugged as follows:

210' of 8 5/8" surface pipe, cemented with 175 sacks. Hole was filled
with drilling mud to 240'. 1st cementing plug was set at 240', bridged
solid with hulls, and cemented with 25 sacks, bringing the cement to
163' in the surface pipe. Hole was filled with drilling mud to 40',
2nd cementing plug, bridged with hulls, and cemented with 10 sacks to
base cellar. Rat hole bridged and cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 2/27/64
INV. NO. 8684-W