

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

FEB 14 1964

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Drillers Production Co., Inc. 15-695-00333 0000

Complete Address: 1020 Union National Bldg., Wichita, Kansas

Lease Name Carl Garnett Well No. # 1

Location C NE NE SW Sec. 35 Twp. 28 Rge. 6 (E) (W)W

County Kingman Total Depth 4337

Abandoned Oil Well Gas Well X Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: Knight Casing Pulling Co.

Address: Box 304, Chase, Kansas License No. 436

Operation Completed: Hour 1:00PM Day 11th Month Feb. Year 1964

The Above well was plugged as follows:

262' of 8 5/8" surface pipe, cement circulated. 4335' of 5 1/2" long string,
cemented with 200 sacks. Plug back to 3960'. Top perforation 3844'. Bottom
of hole was sanded to 3925', and cemented with 5 sacks. Hole was bailed
down to 280', plug was set at 280', with 10' rock bridge, and cemented
with 25 sacks. Hole was filled with mud to 40', with 10' rock bridge,
and cemented with 10 sacks to base cellar.
1400' of 5 1/2" long string was recovered from the hole.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 2/14/64

INV. NO. 8649-4