

KANSAS

JP

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
AUG 30 1971
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Misco Supply Co.

Complete Address 257 N. Broadway Wichita, Ks

Lease Name Mollie Greenwood Well No. 5

Location C NE/SW Sec. 27 Twp. 29 Rge. 18 (E) (W) W

County Kiowa Total Depth 4990

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Pipe Pullers, Inc.

Address Box 486 Ellinwood, Ks License No. 462

Operation Completed: Hour 4:00 PM Day 26 Month 8 Year 1971

The above well was plugged as follows:

409 ft 10 3/4 surface pipe cemented with 325 sacks. 4985 ft 5 1/2 long
string cemented with 225 sacks. Open hole, Sand back to 4950 ft,
5 sacks cement with bailer. Pulled 2711ft of 5 1/2. Set 20 ft rock
bridge at 260 ft. Fill hole with 6 yds redimix to surface.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *M. Russell B. Bristow*
Well Plugging Supervisor

DATE 8-31-71

INV. NO. 4241-U