

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION

AUG 26 1974

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Misco Industries Inc
Complete Address 257 N Broadway Wichita, KS
Lease Name Greenwood Well No. 6
Location C SE/SW Sec. 27 Twp. 29 Rge. 18 (E) (W) W
County Kiowa Total Depth 4979
Abandoned Oil Well X Gas Well _____ Input Well _____ SWD Well _____ D & A _____
Other well as hereafter indicated _____
Plugging Contractor Pipe Pullers Inc
Address Box 486 Ellinwood, KS License No. 462
Operation Completed: Hour 10:00 AM Day 22 Month 8 Year 1974

The above well was plugged as follows:

400 ft 10" surface cemented with 325 sacks. 4975 ft 7" long string
cemented with 200 sacks. Top perf. 4864 ft. Sand to 4500 ft, 7 sacks
cement with bailer. Pulled 2680 ft 7". Set 10 ft rock bridge at
200 ft. Fill hole with 4 yds redimix to surface.

I hereby certify that the above well was plugged as herein stated.

Signed: Russell Bikerstein
Well Plugging Supervisor

INVOICED

DATE 8/27/74
INV. NO. 9772-W