

KANSAS

4 STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 6 1971  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Misco Supply Co.

Complete Address 257 N. Broadway Wichita, Ks

Lease Name Mollie Greenwood Well No. 4

Location C SW/SW Sec. 27 Twp. 29 Rge. 18 (E) (W) W

County Kiowa Total Depth 4934

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor Pipe Pullers, Inc.

Address Box 486 Ellinwood, Ks License No. 462

Operation Completed: Hour 11:00 AM Day 4 Month 8 Year 1971

The above well was plugged as follows:

409 ft 10 3/4 surface pipe cemented with 125 sacks. 4930 ft 5 1/2 long  
string cemented with 225 sacks. Open hole. Sand back to 4900 ft,  
5 sacks cement with bailer. Pulled 3119 ft 5 1/2. Set 20 ft rock bridge  
at 260 ft. Fill hole with 6 yds redimix to surface.

I hereby certify that the above well was plugged as herein stated

Signed: A. Russell Bikerstein  
Well Plugging Supervisor

INVOICED

DATE 8-6-71

INV. NO. 4103-W