

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

JUL 22 1971

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Misco Supply Co.

Complete Address 257 N. Broadway Wichita, Ks

Lease Name Mollie Greenwood Well No. 2

Location C SE/NW Sec. 27 Twp. 29 Rge. 18 (E) (W) W

County Kiowa Total Depth 5085

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Pipe Pullers, Inc.

Address Box 486 Ellinwood, Ks License No. 462

Operation Completed: Hour 11:00 AM Day 19 Month 7 Year 1971

The above well was plugged as follows:

387 ft 10 3/4 surface pipe cemented with 300 sacks. 5070 ft 5 1/2 long
string cemented with 250 sacks. Open hole. Sand back to 5000 ft,
5 sacks cement with bailer. Pulled 3523 ft 5 1/2. Set 20 ft rock
bridge at 300 ft, & fill hole with 6 yds redimix.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]
Well Plugging Supervisor

DATE 7-22-71
INV. NO. 4036-W