

KANSAS  
STATE CORPORATION COMMISSION

## CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Assistant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

RECEIVED  
STATE CORPORATION COMMISSION

JAN 3 1966

CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Woods Petroleum-Kenneth Rupp

Complete Address: 1035 Wichita Plaza, Wichita, Kansas

Lease Name Nichols Well No. # 1

Location C SW NE Sec. 35 Twp. 29 Rge. 18 (E) (W) W

County Kiowa Total Depth 5004'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: \_\_\_\_\_

Plugging Contractor: E. K. Edmiston Drilling Company

Address: 501 First National Bank Bldg., Wichita, Ks. License No. \_\_\_\_\_

Operation Completed: Hour 12:00AM Day 30th Month Dec. Year 1965

The Above well was plugged as follows:

400' of 8 5/8" surface pipe, cement circulated with 180 sacks. Hole  
was filled with drilling mud to 300', 1st cementing plug, bridged solid  
with dry cement and hulls on fluid at 300', and cemented with 25 sacks  
cement. Hole was filled with drilling mud to 40', 2nd cementing plug,  
bridged solid with dry cement and hulls on fluid at 40', and cemented  
with 10 sacks to base of the cellar. Rat hole bridged and cemented  
with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

Signed: Archie Elving  
Well Plugging Supervisor

INVOICED

1/4/66  
2540-W