

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
AUG 16 1971
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Misco Supply Co.

Complete Address 257 N. Broadway Wichita, Ks

Lease Name Parkin A Well No. 2

Location C SW/SE Sec. 32 Twp. 29 Rge. 18 (E) (W) W

County Kiowa Total Depth 4965

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Pipe Pullers, Inc.

Address Box 486 Ellinwood, Ks License No. 462

Operation Completed: Hour 10:00 AM Day 12 Month 8 Year 1971

The above well was plugged as follows:

375 ft 8 5/8 surface pipe cemented with 225 sacks. 4952 ft 5 1/2 long
string cemented with 200 sacks. Open hole. Sand back to 4900 ft,
5 sacks cement with bailer. Pulled 2903 ft 5 1/2. Set 20 ft rock
bridge at 260 ft. Fill hole with 4 yds redimix to surface.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: A. Russell Bechtel
Well Plugging Supervisor

DATE 8-18-71
INV. NO. 4172-11