

KANSAS

2

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JUN 28 1972
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Misco Supply Co.

Complete Address 257 N. Broadway Wichita, Ks

Lease Name Brown A Well No. 3

Location G SE/SE Sec. 32 Twp. 29 Rge. 18 (E) (W)

County Kiowa Total Depth 4965

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Ralph Comstock Pipe Pulling Co. Inc.

Address Stafford, Ks License No. 490

Operation Completed: Hour 2:00 PM Day 26 Month 6 Year 1972

The above well was plugged as follows:

332 ft 8 5/8 surface pipe cemented with 250 sacks. 4964 ft 5 1/2 long
string cemented with 250 sacks. Top perf. 4935 ft. Sand back to
4500 ft, 5 sacks cement with bailer. Pulled 2497 ft 5 1/2. Set 10 ft
rock bridge at 220 ft. Fill hole with 3 yds redimix to surface.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *M. Russell Biderstein*
Well Plugging Supervisor

DATE 6/29/72
INV. NO. 5947-11