

KANSAS

 STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

NOV 8 1971

CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Misco Supply Co.

Complete Address 257 N Broadway Wichita, Ks

Lease Name Fay Thorn Well No. 1

Location C SW/SE Sec. 21 Twp. 29 Rge. 18 (E) (W) W

County Kiowa Total Depth 5095

Abandoned Oil Well X Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A \_\_\_\_\_

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor Pipe Pullers, Inc.


Address Box 486 Ellinwood, Ks License No. 462

Operation Completed: Hour 3:00 PM Day 5 Month 11 Year 1971

The above well was plugged as follows:  
376 ft 8 5/8 surface pipe cemented with 250 sacks. 5094 ft 5 1/8 long  
string cemented with 240 sacks. Plug back to 5050 ft. Sand back to  
5000 ft, 5 sacks cement with bailer. Pulled 2700 ft 5 1/8. Set 20 ft  
rock bridge at 260 ft. Fill hole with 5 yds redimix to surface.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed:   
Well Plugging Supervisor

DATE 11-11-71

INV. NO. 4610-W