

KANSAS

Y STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
MAR 17 1972
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Misco Supply Co.

Complete Address 257 N Broadway Wichita, Ks

Lease Name Fay Thorn Well No. 3

Location C NW/SE Sec. 21 Twp. 29 Rge. 18 (E) (W) W

County Kiowa Total Depth 5070

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Russ Casing Pulling Co.

Address Box 1082 Great Bend, Ks License No. 623

Operation Completed: Hour 2:00 PM Day 15 Month 3 Year 1972

The above well was plugged as follows:

411 ft 8 5/8 surface pipe cemented with 200 sacks. 5070 ft 5 1/2 long
string cemented with 125 sacks. Top perf. 4978 ft. Sand back to
4900 ft, 5 sacks cement with bailer. Pulled 3230 ft 5 1/2. Set 10 ft
rock bridge at 220 ft. Fill hole with 3 yds redimix to surface.

I hereby certify that the above well was plugged as herein stated.

Signed *Russell B. Bilton*
Well Plugging Supervisor

INVOICED

DATE 3-17-72

INV. NO. 5365-4