

KANSAS

K STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION
MAR 31 1972
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Misco Supply Co.

Complete Address 257 N Broadway Wichita, Ks

Lease Name J.P UNruh B Well No. 4

Location C NW/SW Sec. 21 Twp. 29 Rge. 18 (E) (W) W

County Kiowa Total Depth 5140

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Russ Casing Pulling Co.

Address Box 1182 Great Bend, Ks License No. 623

Operation Completed: Hour 11:00 AM Day 29 Month 3 Year 1972

The above well was plugged as follows:

492 ft 8 5/8 surface pipe cemented with 300 sacks. 5138 ft 5 1/2 long
string cemented with 125 sacks. Top perf. 5008 ft. Sand back to
5000 ft, 5 sacks cement with bailer. Pulled 2830 ft 5 1/2. Set 10 ft
rock bridge at 220 ft. Fill hole with 3 yds redimix to surface.

I hereby certify that the above well was plugged as herein stated

Signed: *M Russell Bledsoe*
Well Plugging Supervisor

INVOICED

DATE 3-31-72

INV. NO. 5450-W