

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
CONSERVATION COMMISSION
JUN 01 1978
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 -095-20469-0000 (of this well)

Operator's Full Name Papco Inc.

Complete Address 245 S. Terrace, Wichita, Kans. - 67218

Lease Name Endicott Well No. 1

Location C-1/2, SW, NW - Sec. 21 Twp. 28^S Rge. 9 (E) (W) X

County Kingman Total Depth 4542

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Lupe Puller, Inc.

Address Box 128 - Ellinwood, Kans. - 67526 License No. 462

Operation Completed: Hour 11:15 AM Day 30 Month May Year 1978

The above well was plugged as follows:

313'-8 5/8" Casing w/ 250 sack Cement - 5 1/2" Casing set @ 4535'
w/ 125 sack Cement - plug back to 4494' - perf. at 4394' - Sand
back to 4340' - Top sand w/ 5 sack mixed Cement w/ dump bailer
Pull 2993' - 5 1/2" Casing - mixed & pump 5 sack bulls - 20 gal
release plug - mixed & pumped 125 sack 50/50 pos mix Cement w/ 2
gal gel to top of Casing - Shut in w/ 300# press -

Pumped by -
Howco - Pratt, Kans. - 67124

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]
Well Plugging Supervisor

INVOICED
DATE 6-1-78
INV. NO. 7377-W