

KANSAS

FORM CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGEN'T REPORT

J. Lewis Breck
Administrator
245 North Water
Wichita, Ks. 67202

API Number 15 095-20361-0000 (of this well)

Operator's Full Name Jay C. Clark

Complete Address 245 S. Terrace, Wichita, Ks. 67202

Lease Name Swander Well No. 1

Location 100' W NE NE SW Sec. 20 Twp. 28s Rge. 9 (E) (W) X

County Kingman Total Depth 4420

Abandoned Oil Well X Gas Well Input Well SWD Well D&A

Other well as hereafter indicated

Plugging Contractor Kelso Casing Pulling.

Address Box 176, Chase, Ks. 67524 License No. 683

Operation Completed: Hour 1:30 PM Day 10 Month 10 Year 1980

The Above well was plugged as follows:

340' 8 5/8" casing w/225 sax cement. 4 1/2" casing set at 4418' w/175
sax cement. Plug back to 4180'. Top pref's at 4126-30'-Sand back to
4100'-Top sand w/4 sax mixed cement w/dump bailer. Pull 3525' casing
Allied mixed & pumped in 8 5/8" casing-8 sax hulls-25 sax gel-125
sax 50/50 posmix cement w/4% gel & 3% cc to top of casing. Shut in
w/850# pressure.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 10-17-80

INV. NO. 3371-W

Signed: [Signature]

Well Plugging Supervisor 1980

STATE CORPORATION COMMISSION
RECEIVED
OCT 21 1980
CONSERVATION DIVISION
Wichita, Kansas