

KANSAS
STATE CORPORATION COMMISSION

Form CP-3
Rev. 6-26-62

15-095-00376-0000

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

AUG 17 1964

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Plains Exploration Company

Complete Address: 1135 Petroleum Club Bldg., Denver 2, Colorado

Lease Name Darlington Well No. # 2

Location SE SW SW Sec. 20 Twp. 28 Rge. 9 (E) (W) W

County Kingman Total Depth 4561

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Self Casing Pulling Company

Address: Route 4, Hutchinson, Kansas License No. 48

Operation Completed: Hour 1:00PM Day 15th Month August Year 1964

The Above well was plugged as follows:

277' of 8 5/8" surface pipe, cemented with 200 sacks. 4540' of 5 1/2" long
string, cemented with 140 sacks. Top perforation 4472'. Bottom of the
hole was sanded to 4450', and cemented with 5 sacks. Fluid in the hole
was bailed down to 260'. Bridge plug was set on fluid at 260', and 10'
of rock bridge, cemented with 25 sacks. Hole was filled with mud to 40',
and 10' of rock bridge, cemented with 10 sacks to the base of the cellar.
3700' of 5 1/2" long string was recovered from the hole.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 8-18-64

INV. NO. 9654-W

Signed: Archie Elving
Well Plugging Supervisor